

# **MEMORANDUM**

To:	City of Arlington CED
	18204 59 <sup>th</sup> Ave NE
	Arlington, WA 98223
Project #:	23118
Date:	August 14, 2023
Subject:	SnoPUD North County Energy Storage Drainage Memorandum

## Section I: Project Overview

The purpose of this memorandum is to provide drainage information for an additional development to the ongoing commercial construction taking place at the North County Facility in Arlington, WA. The project address is 17601 59<sup>th</sup> Ave NE. The project site is approximately 26.5 acres and mostly developed with access roads and various commercial uses. The additional development will consist of the construction of a new solar array on a south-central portion of the site.

The development proposes 45,054 sf (1.03 sf) of new impervious surface and will adhere to the Minimum Requirements #1-9 of the 2019 Stormwater Management Manual for Western Washington (SWMMWW). Since the project site has several permits which have been approved for construction and one project currently in construction, this report is provided to supplement the existing permit, providing additional flow control discussion for the new areas.

Site soils consist of advance outwash with a design infiltration rate of 17 in/hr. Groundwater was discovered approximately 5 feet below grade, but groundwater is not expected to be an issue so long as the vertical separation requirements are met. The geotechnical report for the project is provided in Section IV. The project proposes to install several surface infiltration swales located under the proposed solar array.



Figure I-1 – Project Site (Google Maps)

## Section II: Minimum Requirements

Stormwater requirements were determined from the 2019 SWMMWW. This report is based on the steps recommended in Chapter 3 of Volume I in the SWMMWW. The project will comply with Minimum Requirements #1-9.

<u>Minimum Requirement #1: Preparation of Stormwater Site Plans:</u> The stormwater site plan consists of this report and the civil drawings and is prepared in accordance with Chapter 3 of Volume 1 of the SWMMWW.

<u>Minimum Requirement #2: Construction Stormwater Pollution Prevention Plan (SWPPP):</u> The SWPPP shall include a narrative and drawings. The SWPPP narrative shall include documentation that addresses the 13 elements of Construction Stormwater Pollution Prevention. A SWPPP and Construction Stormwater General Permit have been approved for the current construction.

<u>Minimum Requirement #3: Source Control of Pollution:</u> Source control BMPs during construction have been addressed in previous reports and are implemented in the current construction.

<u>Minimum Requirement #4: Preservation of Natural Drainage Systems and Outfalls:</u> Natural drainage patterns shall be maintained, and discharges from the project site shall occur at the natural location, to the maximum extent practicable. The manner by which runoff is discharged from the project site must not cause a significant adverse impact to downstream receiving waters and down-gradient properties. The site is naturally very flat and infiltrates at a high rate. The project will infiltrate in the proposed condition. A full off-site analysis has been completed as part of past projects and is not required for additional development.

<u>Minimum Requirement #5: On-Site Stormwater Management:</u> New development projects on any parcel inside the Urban Growth Area that trigger Minimum Requirements #1 through #9 must demonstrate compliance with the Low Impact Development Performance Standard and BMP T5.13; or use On-Site Stormwater Management BMPs from List #2. The project will meet the LID performance standard with infiltration swales. See Section III.

<u>Minimum Requirement #6: Runoff Treatment:</u> This requirement applies to projects that add more than 5,000 sf of new/replaced Pollution Generating Hard Surface (PGHS) or 3/4 of an acre of Pollution Generating Pervious Surface (PGPS). The project hard surface is not subject to regular vehicular use and is not considered pollution generating. See Section III for further explanation.

<u>Minimum Requirement #7: Flow Control:</u> Projects must provide flow control to reduce the impacts of stormwater runoff from hard surfaces and land cover conversions. The project will meet the flow control duration standard using infiltration swales. See Section III.

Minimum Requirement #8: Wetlands Protection: There are no wetlands near the project site.

<u>Minimum Requirement #9: Operation and Maintenance</u>: Operation and maintenance manuals are included in pervious reports which include maintenance procedures for the BMPs the project is proposing.

#### Section III: Permanent Stormwater Control Plan

<u>On-Site Stormwater Management:</u> The project will meet the LID performance standard by providing a system of fully infiltrating surface infiltration swales. These swales are designed to take on sheet flow from the surrounding impervious asphalt. The swale section consists of uncompacted native soils with a design infiltration rate of 17 in/hr. This infiltration rate is provided by the geotechnical engineer in their "Stormwater Management Analysis Considerations" report. Refer to Section IV for this report and the infiltration WWHM report.



250 4th Avenue South, Suite 200 Edmonds, WA 98020 ph. 425.778.8500 | f. 425.778.5536 www.cgengineering.com <u>Runoff Treatment:</u> The project proposes to be exempt from the runoff treatment requirements since the site impervious areas are not considered pollution generating. The SWMMWW defines PGIS as impervious surfaces subject to vehicular use. Per the SWMMWW definition, infrequently used maintenance access roads are not considered as being subject to regular vehicular use. Since the road will only be used for infrequent maintenance, the site impervious is not considered pollution generating, and runoff treatment is not required.

<u>Flow Control</u>: The project adds greater than 10,000 sf of new impervious surface, and flow control is required. The project proposes to meet the flow control standard with the infiltration system as described above. Refer to Section IV for the WWHM report.

#### Section IV: Attachments

- WWHM Infiltration Report
- Stormwater Management Analysis Considerations Report
- Geotechnical Engineering Report

Please reach out to us with any questions.

Sincerely, *CG Engineering* 

Juiller

Greg Guillen, PE, SE Principal

DISCLAIMER

This recommendation is the professional opinion of CG Engineering PLLC based on the information provided. This memo was prepared subject to the standard of care applicable to professional services at the time the services were provided.



250 4th Avenue South, Suite 200 Edmonds, WA 98020 ph. 425.778.8500 | f. 425.778.5536 www.cgengineering.com

#### WWHM2012 PROJECT REPORT

Project Name: SnoPUD North County Infiltration 08.02.23
Site Name:
Site Address:
City :
Report Date: 8/2/2023
Gage : Everett
Data Start : 1948/10/01
Data End : 2009/09/30
Precip Scale: 1.20
Version Date: 2019/09/13
Version : 4.2.17

Low Flow Threshold for POC 1 : 50 Percent of the 2 Year

High Flow Threshold for POC 1: 50 year PREDEVELOPED LAND USE Name : Basin 1 Bypass: No GroundWater: No acre Pervious Land Use A B, Forest, Flat 1.03 1.03 Pervious Total Impervious Land Use acre Impervious Total 0 1.03 Basin Total Element Flows To: Surface Interflow Groundwater MITIGATED LAND USE Name : Lateral I Basin 1 Bypass: No Impervious Land Use acre

0.48

ROADS FLAT LAT

Element Flows To: Outlet 1 Outlet 2 Gravel Trench Bed 1

```
Name : Gravel Trench Bed 1
Bottom Length: 1676.00 ft.
Bottom Width: 11.50 ft.
Trench bottom slope 1: 0 To 1
Trench Left side slope 0: 0.33 To 1
Trench right side slope 2: 0.33 To 1
Material thickness of first layer: 0.5
Pour Space of material for first layer: 1
Material thickness of second layer: 0
Pour Space of material for second layer: 0
Material thickness of third layer: 0
Pour Space of material for third layer: 0
Infiltration On
Infiltration rate: 17
Infiltration safety factor: 1
Total Volume Infiltrated (ac-ft.): 167.549
Total Volume Through Riser (ac-ft.): 0
Total Volume Through Facility (ac-ft.): 167.549
Percent Infiltrated: 100
Total Precip Applied to Facility: 79.401
Total Evap From Facility: 4.358
Discharge Structure
Riser Height: 0 ft.
Riser Diameter: 0 in.
```

Element Flows To: Outlet 1 Outlet 2

	Gravel	Trench Bed	Hydraulic Tab	le
Stage(feet)	Area(ac.)	Volume(ac-ft.	) Discharge(cfs)	Infilt(cfs)
0.0000	0.442	0.000	0.000	0.000
0.0056	0.442	0.002	0.000	7.584
0.0111	0.442	0.004	0.000	7.584
0.0167	0.442	0.007	0.000	7.584
0.0222	0.443	0.009	0.000	7.584
0.0278	0.443	0.012	0.000	7.584
0.0333	0.443	0.014	0.000	7.584
0.0389	0.443	0.017	0.000	7.584
0.0444	0.443	0.019	0.000	7.584
0.0500	0.443	0.022	0.000	7.584
0.0556	0.443	0.024	0.000	7.584
0.0611	0.444	0.027	0.000	7.584
0.0667	0.444	0.029	0.000	7.584
0.0722	0.444	0.032	0.000	7.584
0.0778	0.444	0.034	0.000	7.584

0.0833	0.444	0.037	0.000	7.584
0.0889	0.444	0.039	0.000	7.584
0 0944	0 444	0 041	0 000	7 584
0 1000	0.445	0.011	0.000	7 584
0.1056	0.445	0.044	0.000	7.504
0.1000	0.445	0.040	0.000	7.504
0.1111	0.445	0.049	0.000	7.584
0.116/	0.445	0.051	0.000	7.584
0.1222	0.445	0.054	0.000	7.584
0.1278	0.445	0.056	0.000	7.584
0.1333	0.445	0.059	0.000	7.584
0.1389	0.446	0.061	0.000	7.584
0.1444	0.446	0.064	0.000	7.584
0.1500	0.446	0.066	0.000	7.584
0.1556	0.446	0.069	0.000	7.584
0.1611	0.446	0.071	0.000	7.584
0.1667	0.446	0.074	0.000	7.584
0.1722	0.446	0.076	0.000	7.584
0 1778	0 447	0 079	0 000	7 584
0 1833	0.447	0.081	0.000	7 584
0.1889	0.447	0.001	0.000	7 584
0.1044	0.447	0.004	0.000	7.504
0.1944	0.447	0.000	0.000	7.504
0.2000	0.447	0.009	0.000	7.504
0.2056	0.447	0.091	0.000	7.584
0.2111	0.44/	0.094	0.000	7.584
0.2167	0.448	0.096	0.000	7.584
0.2222	0.448	0.099	0.000	7.584
0.2278	0.448	0.101	0.000	7.584
0.2333	0.448	0.103	0.000	7.584
0.2389	0.448	0.106	0.000	7.584
0.2444	0.448	0.108	0.000	7.584
0.2500	0.448	0.111	0.000	7.584
0.2556	0.449	0.113	0.000	7.584
0.2611	0.449	0.116	0.000	7.584
0.2667	0.449	0.118	0.000	7.584
0.2722	0.449	0.121	0.000	7.584
0.2778	0.449	0.123	0.000	7.584
0.2833	0.449	0.126	0.000	7.584
0.2889	0.449	0.128	0.000	7.584
0.2944	0.449	0.131	0.000	7.584
0.3000	0.450	0.133	0.000	7.584
0.3056	0.450	0.136	0.000	7.584
0.3111	0.450	0.138	0.000	7.584
0.3167	0.450	0.141	0.000	7.584
0 3222	0 450	0 143	0 000	7 584
0 3278	0 450	0 146	0 000	7 584
0 3333	0.450	0 148	0.000	7 584
0.3389	0.450	0.151	0.000	7 584
0.3444	0.451	0.153	0.000	7 584
0.3500	0.451	0.155	0.000	7 584
0.3500	0.451	0.150	0.000	7.504
0.3330	0.401 0 /51	0.100	0.000	7 504
0.3011	0.401 0 /F1	0.101	0.000	1.304 7 FO/
0.300/	0.431 0.451	0.103	0.000	7.504
0.3720	0.431	0.100	0.000	1.384
0.3//8	0.452	0.109	0.000	1.584
0.3833	0.452	$\cup . \perp / \perp$	0.000	/.584
0.3889	0.452	$\cup . \perp / 4$	0.000	/.584
0.3944	0.452	U.1/6	0.000	/.584

0.4000	0.452	0.179	0.000	7.584
0.4056	0.452	0.181	0.000	7.584
0.4111	0.452	0.184	0.000	7.584
0.4167	0.453	0.186	0.000	7.584
0.4222	0.453	0.189	0.000	7.584
0.4278	0.453	0.191	0.000	7.584
0.4333	0.453	0.194	0.000	7.584
0.4389	0.453	0.196	0.000	7.584
0.4444	0.453	0.199	0.000	7.584
0.4500	0.453	0.201	0.000	7.584
0.4556	0.454	0.204	0.000	7.584
0.4611	0.454	0.206	0.000	7.584
0.4667	0.454	0.209	0.000	7.584
0.4722	0.454	0.211	0.000	7.584
0.4778	0.454	0.214	0.000	7.584
0.4833	0.454	0.216	0.000	7.584
0.4889	0.454	0.219	0.000	7.584
0.4944	0.455	0.221	0.000	7.584
0.5000	0.455	0.224	0.000	7.584

#### ANALYSIS RESULTS

Stream Protection Duration

Predeveloped Landuse Totals for POC #1 Total Pervious Area:1.03 Total Impervious Area:0

Mitigated Landuse Totals for POC #1 Total Pervious Area:0 Total Impervious Area:0.48

Flow Frequency	Return	Periods	for	Predevelope	d. POC #1
Return Period		Flow(cfs	3)		
2 year		0.0011	182		
5 year		0.0025	564		
10 year		0.0041	L13		
25 year		0.0071	L84		
50 year		0.0106	515		
100 year		0.0153	398		
Flow Frequency	Return	Periods	for	Mitigated.	POC #1
Return Period		Flow(cfs	3)		
2 year		0			
5 year		0			
10 year		0			
25 year		0			
50 year		0			
100 year		0			

Annual	Peaks	for Predevelo	ped and Mitigated.	POC #	1
Year		Predeveloped	Mitigated		
1949		0.001	0.000		
1950		0.002	0.000		
1951		0.002	0.000		
1952		0.001	0.000		
1953		0.001	0.000		
1954		0.006	0.000		
1955		0.004	0.000		
1956		0.001	0.000		
1957		0.001	0.000		
1958		0.001	0.000		
1959		0.002	0.000		
1960		0.002	0.000		
1961		0.004	0.000		
1962		0.001	0.000		
1963		0.001	0.000		
1964		0.003	0.000		
1965		0.001	0.000		
1966		0.001	0.000		
1967		0.002	0.000		
1968		0.001	0.000		
1969		0.001	0.000		
1970		0.001	0.000		
1971		0.004	0.000		
1972		0.001	0.000		
1973		0.001	0.000		
1974		0.002	0.000		
1975		0.001	0.000		
1976		0.002	0.000		
1977		0.001	0.000		
1978		0.001	0.000		
1979		0.002	0.000		
1980		0.001	0.000		
1981		0.001	0.000		
1982		0.001	0.000		
1983		0.001	0.000		
1984		0.001	0.000		
1985		0.001	0.000		
1986		0.007	0.000		
1987		0.005	0.000		
1988		0.001	0.000		
1989		0.001	0.000		
1990		0.001	0.000		
1991		0.001	0.000		
1992		0.001	0.000		
1993		0.001	0.000		
1994 1005		0.001	0.000		
1995 1006		U.UUI	0.000		
1996 1007		0.009	0.000		
199/		0.025	0.000		
1998 1999		U.UUI 0.001	0.000		
7999 7933		0.001	0.000		
2000 2001		0.002	0.000		
ZUUI		0.001	0.000		

Stream Protection Duration

2002	0.001	0.000
2003	0.001	0.000
2004	0.001	0.000
2005	0.001	0.000
2006	0.027	0.000
2007	0.001	0.000
2008	0.001	0.000
2009	0.001	0.000

Stream	Protection Durat:	ion	
Ranked	Annual Peaks for	Predeveloped and Mitigated	. POC #1
Rank	Predeveloped	Mitigated	
1	0.0274	0.0000	
2	0.0255	0.0000	
3	0.0093	0.0000	
4	0.0072	0.0000	
5	0.0057	0.0000	
6	0.0048	0.0000	
7	0.0043	0.0000	
8	0.0040	0.0000	
9	0.0039	0.0000	
10	0.0027	0.0000	
	0.0024	0.0000	
12	0.0022	0.0000	
13	0.0019	0.0000	
14	0.0019	0.0000	
15	0.0017	0.0000	
10	0.0016	0.0000	
1 /	0.0016	0.0000	
10	0.0015	0.0000	
19	0.0015	0.0000	
20	0.0014	0.0000	
22	0.0012	0.0000	
22	0.0012	0.0000	
23	0.0010	0.0000	
25	0.0008	0.0000	
25	0.0008	0.0000	
27	0 0008	0 0000	
28	0 0008	0 0000	
29	0 0008	0 0000	
30	0.0008	0.0000	
31	0.0008	0.0000	
32	0.0008	0.0000	
33	0.0008	0.0000	
34	0.0008	0.0000	
35	0.0008	0.0000	
36	0.0008	0.0000	
37	0.0008	0.0000	
38	0.0008	0.0000	
39	0.0008	0.0000	
40	0.0008	0.0000	
41	0.0008	0.0000	
42	0.0008	0.0000	
43	0.0008	0.0000	
44	0.0008	0.0000	

45	0.0008	0.0000
46	0.0008	0.0000
47	0.0008	0.0000
48	0.0008	0.0000
49	0.0008	0.0000
50	0.0008	0.0000
51	0.0008	0.0000
52	0.0008	0.0000
53	0.0008	0.0000
54	0.0008	0.0000
55	0.0008	0.0000
56	0.0008	0.0000
57	0.0008	0.0000
58	0.0008	0.0000
59	0.0008	0.0000
60	0.0007	0.0000
61	0.0006	0.0000

#### Stream Protection Duration POC #1 The Facility PASSED

# The Facility PASSED.

Flow(cfs)	Predev	Mit	Percentage	Pass/Fail
0.0006	2357	0	0	Pass
0.0007	1329	0	0	Pass
0.0008	437	0	0	Pass
0.0009	112	0	0	Pass
0.0010	102	0	0	Pass
0.0011	89	0	0	Pass
0.0012	77	0	0	Pass
0.0013	66	0	0	Pass
0.0014	61	0	0	Pass
0.0015	58	0	0	Pass
0.0016	54	0	0	Pass
0.0017	50	0	0	Pass
0.0018	49	0	0	Pass
0.0019	47	0	0	Pass
0.0020	43	0	0	Pass
0.0021	40	0	0	Pass
0.0022	36	0	0	Pass
0.0023	36	0	0	Pass
0.0024	32	0	0	Pass
0.0025	31	0	0	Pass
0.0026	31	0	0	Pass
0.0027	29	0	0	Pass
0.0028	29	0	0	Pass
0.0029	27	0	0	Pass
0.0030	26	0	0	Pass
0.0031	26	0	0	Pass
0.0032	26	0	0	Pass
0.0033	25	0	0	Pass
0.0034	23	0	0	Pass
0.0035	23	0	0	Pass
0.0036	23	0	0	Pass

0.0037	23	0	0	Pass
0.0038	23	0	0	Pass
0.0039	21	0	0	Pass
0.0040	19	0	0	Pass
0.0041	18	0	0	Pass
0.0042	17	0	0	Pass
0.0043	16	0	0	Pass
0.0044	16	0	0	Pass
0.0045	15	0	0	Pass
0.0046	15	0	0	Pass
0.0047	14	0	0	Pass
0.0048	13	0	0	Pass
0.0049	13	0	0	Pass
0.0050	13	0	0	Pass
0.0051	13	0	0	Pass
0.0052	13	0	0	Pass
0.0053	13	0	0	Pass
0.0055	13	0	0	Pass
0.0056	13	0	0	Pass
0.0057	13	0	0	Pass
0.0058	11	0	0	Pass
0.0059	11	0	0	Pass
0.0060	11	0	0	Pass
0.0061	11	0	0	Pass
0.0062	11	0	0	Pass
0.0063	11	0	0	Pass
0.0064	11	0	0	Pass
0.0065	11	0	0	Pass
0.0066	11	0	0	Pass
0.0067	11	0	0	Pass
0.0068	11	0	0	Pass
0.0069	11	0	0	Pass
0.0070	11	0	0	Pass
0.0071	10	0	0	Pass
0.0072	10	0	0	Pass
0.0073	9	0	0	Pass
0.0074	9	0	0	Pass
0.0075	8	0	0	Pass
0.0076	8	0	0	Pass
0.0077	8	0	0	Pass
0.0078	8	0	0	Pass
0.0079	8	0	0	Pass
0.0080	8	0	0	Pass
0.0081	8	0	0	Pass
0.0082	8	0	0	Pass
0.0083	8	0	0	Pass
0.0084	8	0	0	Pass
0.0085	8	0	0	Pass
0.0086	8	0	0	Pass
0.0087	8	0	0	Pass
0.0088	8	0	0	Pass
0.0089	8	0	0	Pass
0.0090	7	0	U	Pass
0.0091	7	0	U	Pass
0.0092	7	0	0	Pass
0.0093	7	0	0	Pass
0.0094	6	0	0	Pass

0.0095	6	0	0	Pass
0.0096	6	0	0	Pass
0.0097	6	0	0	Pass
0.0098	6	0	0	Pass
0.0099	6	0	0	Pass
0.0100	6	0	0	Pass
0.0101	6	0	0	Pass
0.0102	6	0	0	Pass
0.0103	6	0	0	Pass
0.0104	6	0	0	Pass
0.0105	5	0	0	Pass
0.0106	5	0	0	Pass

Water Quality BMP Flow and Volume for POC #1 On-line facility volume: 0 acre-feet On-line facility target flow: 0 cfs. Adjusted for 15 min: 0 cfs. Off-line facility target flow: 0 cfs. Adjusted for 15 min: 0 cfs.

#### LID Report

LID Techniq	ue	Used for	Total Volume	Volume	Infiltration	Cumulative
Percent	Water Quality	Percent	Comment			
		Treatment	? Needs	Through	Volume	Volume
Volume		Water Qualit	У	-		
			Treatment	Facility	(ac-ft.)	Infiltration
Infiltrated		Treated				
			(ac-ft)	(ac-ft)		Credit
Gravel Tren	ch Bed 1 POC	N	152.47			N
100.00						
Total Volume	e Infiltrated		152.47	0.00	0.00	
100.00	0.00	0 %	No Treat. Cre	dit		
Compliance v	with LID Standa	rd 8				
Duration Analysis Result = Pas		Passed				

## Perlnd and Implnd Changes

No changes have been made.

This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2023; All Rights Reserved.

## **Stormwater Management Analysis Considerations**

The site is underlain by permeable native granular soil and is characterized by a relatively shallow seasonal groundwater condition. Conclusions regarding stormwater infiltration feasibility can be drawn from subsurface conditions disclosed by the subsurface explorations, groundwater observations, and laboratory testing completed to date.

We understand that stormwater management improvements will be designed in accordance with the Washington State Department of Ecology 2019 *Stormwater Management Manual for Western Washington (Manual)*. We collected representative samples of shallow soils and completed mechanical grain size tests as part of assessing the soils' saturated hydraulic conductivity, as summarized below.

# Saturated Hydraulic Conductivity

The *Manual* allows a determination of soil saturated hydraulic conductivity to be estimated based on grain size distribution characteristics in accordance with the following formula:

Log10 ( $K_{sat, initial}$ ) = -1.57 + 1.9 $D_{10}$  + 0.015 $D_{60}$  – 0.013 $D_{90}$  -2.08 $f_{fines}$  where:

 $K_{sat, initial}$  = initial saturated hydraulic conductivity in centimeters/second prior to the application of correction factors

 $D_{10}$  = grain size diameter (mm) for which 10 percent of the sample by weight is finer

 $D_{60}$  = grain size diameter (mm) for which 60 percent of the sample by weight is finer

 $D_{90}$  = grain size diameter (mm) for which 90 percent of the sample by weight is finer

 $f_{\text{fines}}$  = fraction of the sample by weight that passes the US No. 200 sieve.

The calculated hydraulic conductivity values for representative soils that we tested are listed in the table below. Grain size distribution curves for the samples are presented in Appendix B.

Table 9: Saturated Hydraulic Conductivity Summary			
Exploration / Sample	Approximate sample depth	Unfactored Saturated Hydraulic	
	(feet)	Conductivity	
		(inches per hour)	
B-1 / S-5	10	41.3	
B-2 / S-3	5	50.6	
TP-1 / S-1	2.5	48.5	
TP-1 / S-2	4	59.2	
TP-1 / S-3	6-1/2	80.3	

Table 9: Saturated Hydraulic Conductivity Summary			
Exploration / Sample	Approximate sample depth (feet)	Unfactored Saturated Hydraulic Conductivity (inches per hour)	
TP-6 / S-1	1	34.7	
TP-6 / S-2	4	58.5	
TP-6 / S-3	7-1/2	105.8	

# Design Saturated Hydraulic Conductivity Rate

The *Manual* requires applying correction factors to the baseline saturated hydraulic conductivity rate. Table 3.3.1 *Correction Factors to be Used with In-Situ Saturated Hydraulic Conductivity Measurements to Estimate Design Rates* of the *Manual* calls for 40 percent reduction of the baseline rate determined via the grain size method ( $CF_{\tau}$ ). Table 3.3.1 also requires applying correction factors for site variability and number of locations tested ( $CF_{\nu}$ ) and the degree of influent control to prevent siltation and bio-buildup ( $CF_{M}$ ). Based upon the site conditions, testing, and our experience with projects of a similar nature, we applied values of 0.5, 0.4, and 0.9 for  $CF_{\nu,} CF_{\tau,}$  and  $CF_{M,}$ , respectively. We recommend using a factored rate ( $K_{sat}$ ) of 17 inches/hour for the *in situ* native outwash sand and gravel for purposes of stormwater infiltration analysis.

Construction of the substation will include selective removal of existing uncontrolled fill material prior to placing imported granular fill to foundation and slab subgrade elevations as necessary. This densification will reduce the site soil's infiltration rate compared to the underlying less dense *in situ* soils. However, this process is only recommended for below foundations and slabs; it is not recommended for the balance of the yard in order to promote stormwater infiltration.

# Groundwater Considerations

Previous groundwater monitoring by GeoEngineers included recording a seasonal high elevation of approximately 130-1/2 feet, or about 5-1/2 feet below existing grade and likely about 6-1/2 feet below substation finished grade. The depth of groundwater is not likely to adversely affect the substation's ability to adequately infiltrate stormwater falling on the site, in our opinion.

# Storage Considerations

The substation yard will be mantled with a 4-inch compacted thickness of "substation rock" underlain by WSDOT CSBC per Specification 9-03.9(3). The substation rock is used for safety purposes as it has a very high void ratio and electrical resistivity and its use reduces the likelihood of step potentials developing. The high void ratio of the substation rock and the CSBC are also beneficial from the stormwater management perspective because over the course of design and construction of numerous substations and switching stations it has been shown that these materials provide useful storage capacity.

As part of previous District substation projects, ZGA and others have tested CSBC sourced from the Iron Mountain Quarry in Granite Falls, Washington. Samples of this material, when compacted to approximately 95 percent density per ASTM D 1557, have been shown to have a permeability of 130 inches/hour and void ratio of over 40 percent. In contrast to some other locally available CSBC, the Iron Mountain Quarry products are 100 percent crushed rock and no naturally occurring bank run sand is blended with the crushed rock to produce the finished product. Based on the testing, the crushed products from Iron Mountain Quarry tend to have a high permeability and void ratio compared to some other locally available products that combine crushed rock and bank run sand and this is a function of the overall low fine to medium sand content and the fines content (the fraction of soil particles finer than the US No. 200 sieve) and angularity of the products. Below we have excerpted a section from the 30 November 2012 geotechnical engineering report prepared by Terracon Consultants, Inc. which summarizes testing completed on a sample of CSBC sourced from the Iron Mountain Quarry.

## Geotechnical Engineering Report

Cedar Valley Substation Snohomish County, Washington 30 November 2012 Terracon Project No.: 81125096



We collected a sample of material meeting the criteria for WSDOT Specification 9-03.9(3) *Crushed Surfacing* (base course gradation). The sample was compacted to 95 percent of the modified Proctor maximum dry density (ASTM D 1557) and the permeability determined. Test results are summarized below.

Summary of Crushed Surfacing Laboratory Testing					
Supplier / Location	Dry Density (ASTM D 1557)	Compaction (percent)	Specific Gravity (data provided by WSDOT)	Void Ratio	Permeability (inches/hour)
Iron Mountain Quarry / Granite Falls	120.6	95.0	2.75	0.424	130

It should be noted that the testing was completed on the sample fraction passing the US No. <sup>3</sup>/<sub>4</sub>inch sieve for compliance with ASTM D 1557. Actually field values will vary slightly from the reported values due to the presence of aggregate larger than <sup>3</sup>/<sub>4</sub>-inch and also due to variations in loads. Material placement procedures can also result in aggregate segregation which can produce variable void ratio and permeability values.

It has been our experience that the crushed rock base course that is produced completely from crushed rock and not including any bank-run material is generally "clean" (lacking finer particles) and this is reflected in the test results.

We recently received from Iron Mountain Quarry the results of recent permeability testing of their CSBC completed by Krazan & Associates, Inc. The test results, which are included in Appendix B, were

conducted on full samples of the CSBC, i.e., the plus 3/4-inch fraction was not removed prior to testing. Consistent with our conclusion pointed out above, the tests indicated permeability rates for two samples of 168.5 to 170.5 inches/hour when compacted to 98 percent of the modified Proctor maximum dry density.

In 2013, ZGA tested what Iron Mountain Quarry was selling as "substation rock" at the time. This was a 1.5-inch minus product, all crushed, and just slightly coarser than the 1.25-inch minus CSBC. The tested material had a void ratio of 45 percent. A photograph of this substation rock is shown below as a means to illustrate its angularity and obvious functional high void ratio even when compacted.



We recommend that imported crushed rock used for both structural fill in the yard and stormwater management purposes have the gradation show in the table below provided that fill with a high void ratio and permeability are required.

Table 10: Recommended Crushed Rock Fill Gradation			
US Standard Sieve Size	Percent Passing by Dry Weight Basis		
1.25 inch	100		
1 inch	80 - 100		
5/8 inch	50 - 80		
No. 4	25 - 45		
No. 40	3 - 18		
No. 200	< 3		

# Groundwater Mounding Analysis

Plans provided for our review indicate that the substation footprint encompasses slightly less than one acre. It appears that groundwater mounding analysis is not necessary per the *Manual* given the documented groundwater depth relative to the anticipated site improvements.

# GEOTECHNICAL ENGINEERING REPORT -DRAFT NORTH COUNTY SPECIAL USE PERMIT 17601 – 59<sup>th</sup> Avenue NE Arlington, Washington

Project No. 2679.01 1 June 2023

Prepared for: Snohomish County PUD No. 1



Prepared by: ZipperGeO

Zipper Geo Associates, LLC 19019 36<sup>th</sup> Avenue W., Suite E Lynnwood, WA 98036



Project No. 2679.01 1 June 2023

Snohomish County PUD No. 1 Distribution & Engineering Services Division, PO Box 1107 Everett, Washington 98206-1107

Attention: Mr. Jerome Drescher, Engineer

Subject: Geotechnical Engineering Report - DRAFT North County Special Use Permit 17601 – 59<sup>th</sup> Avenue NE Arlington, Washington

Dear Mr. Drescher:

In accordance with your request, Zipper Geo Associates, LLC (ZGA) has completed the subsurface exploration and geotechnical engineering evaluation for the proposed North County Special Use Permit project. This report presents the findings of the subsurface exploration and geotechnical recommendations for the project. Our work was completed in general accordance with the scope of services described in Professional Services Contract No. CW2250618 Amendment No. 1. Written authorization to proceed was provided by the District on 15 April 2023. We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report, or if we may be of further assistance, please contact us.

Sincerely, Zipper Geo Associates LLC

#### DRAFT

Justin L. Brooks, LG Project Geologist

#### DRAFT

David C. Williams, LG, LEG Principal Engineering Geologist

Distribution: Addressee (1 electronic) Cover photo courtesy Google Earth

# DRAFT

Robert A. Ross, PE Managing Principal

# TABLE OF CONTENTS

INTRODUCTION1
PROJECT INFORMATION1
Site Description1
Project Description1
Site History2
SITE CONDITIONS
Surface Conditions2
Subsurface Conditions
Groundwater5
CONCLUSIONS AND RECOMMENDATIONS
General Geotechnical Considerations5
Regulated Geologic Hazard Areas6
Earthwork10
Site Preparation11
Structural Fill Placement and Compaction11
Utility Installation Recommendations14
Solar Array Foundation Recommendations15
Stormwater Infiltration Feasibility18
Flexible Pavement Section Recommendations21
Erosion Control
CLOSURE23

# FIGURES

Figure 1 – Site and Exploration Plan

# APPENDICES

Appendix A – Field Exploration Procedures and Logs Appendix B – Laboratory Testing Procedures and Results Appendix C – Liquefaction Analysis Output Plot

# GEOTECHNICAL ENGINEERING REPORT - DRAFT NORTH COUNTY SPECIAL USE PERMIT 17601 – 59<sup>th</sup> AVENUE NE ARLINGTON, WASHINGTON Project No. 2679.01 1 June 2023

# INTRODUCTION

This report summarizes the geotechnical engineering exploration and analysis completed for the proposed North County Special Use Permit project in Arlington, Washington. Eleven test pits (TP-1 through TP-11), and one hand auger boring (HA-1) were completed by ZGA to depths ranging from approximately 6.5 to 10.5 feet below the existing ground surface to evaluate subsurface conditions. We also relied upon subsurface information developed as part of completing the geotechnical exploration and analysis for the planned Crosswind substation in the southeastern portion of the site earlier this year, as well as explorations completed by GeoEngineers as described subsequently. Descriptive logs of the explorations are included in Appendix A while Appendix B contains a summary of laboratory testing procedures and results.

#### **PROJECT INFORMATION**

#### **Site Description**

The project site is located in the southern portion of the District's Arlington Microgrid facility. The site is located 0.2 miles south of 180<sup>th</sup> Street NE and 0.4 miles east of 59<sup>th</sup> Avenue NE and near the BNSF Railroad right-of-way. The railroad right-of-way adjoins the site at the east, industrial/commercial buildings and lots are to the south, and District facilities lie north and east. An asphalt-paved access drive (63<sup>rd</sup> Avenue NE) roughly bisects the site. The site currently includes a previously graded grassy field at the west, a solar array to the east, a gravel-surfaced lot at the southeast (future home of the Crosswind substation), and a District crew training facility at the northeast. A large battery structure is located at the northwest corner of the existing solar array and is part of the power backup storage system. The site and immediate vicinity are illustrated on the *Site and Exploration Plan*, Figure 1.

# **Project Description**

Site improvements planned as part of the Special Use Permit program that are addressed in this report include the following:

- Relocation of a portion of the existing solar array to the open field in the western portion of the site.
- Construction of additional paved parking and materials storage space north of the east end of the relocated solar array and west of 63<sup>rd</sup> Avenue NE.



- Construction of a paved access road that will extend along the southeastern, eastern, and northeastern portions of the site east of 63<sup>rd</sup> Street.
- Stormwater system improvements to accommodate runoff from the new paved access road and parking/storage areas.
- We understand that a new battery backup system will be installed in a portion of the existing solar array facility. However, addressing geotechnical considerations associated with this project element was not included in our scope of services.

# Site History

The District retained GeoEngineers to completed multiple phases of geotechnical exploration and analysis since the District began development of the Microgrid property, and we have relied upon information provided in some of the GeoEngineers reports to supplement ZGA's Special Use Permit-specific exploration and analysis. The GeoEngineers reports that we reviewed are listed below, and selected exploration logs are included in Appendix A:

- GeoEngineers, *Hydrogeologic Assessment, Proposed Pole Yard, Arlington, Washington*, File No. 0482-051-03, dated 26 April 2016;
- GeoEngineers, *Geotechnical Engineering Services, North County Project, Arlington, Washington,* File No. 0482-051-03, dated 29 December 2017;
- GeoEngineers, Updated Groundwater Monitoring Data (Addendum No. 2), North County Project, Arlington, Washington, File 0482-051-04, dated 20 June 2018;
- GeoEngineers, Geotechnical Engineering Services, Update 1 Revision 1, North County Community Office Project, Early Site Development Phase, Arlington, Washington, Field Nol 0482-051-04, dated 5 February 2021.

# SITE CONDITIONS

# **Surface Conditions**

The new solar array site and parking/storage area in the western portion of the site is a relatively level area with ground surface elevations between about 128 and 131 feet. The site is irregularly vegetated with grasses. Water mains have been installed on site and two fire hydrants are located at some distance from each other along the southern border of the site. A pre-cast concrete and steel vault in the north-central portion of the lot contains a groundwater monitoring well monument (GEB-3) installed by GeoEngineers. The District has a large pile of soil material stored at the eastern side of the site. The adjoining 63<sup>rd</sup> Avenue NE to the east side is asphalt-paved, two lanes, and in a serviceable condition.

Crosswind Substation - DRAFT Project No. 2679.01 1 June 2023 During our site visits we observed some isolated puddles following heavy rain, but these drained relatively quickly.

The existing solar array to the east occupies a relatively level area with ground surface elevations ranging from about 133 to 137 feet. The area is vegetated with grasses and supports single-lane gravel-surfaced access drives between the rows of solar panels. Numerous power and fiber optic vaults are located along the west side and adjacent to 63<sup>rd</sup> Avenue NE.

The future Crosswind substation site at the southeast is a relatively level area with ground surface elevations ranging from about 135 to 136 feet. The site is mantled with about 4 to 6 inches of ¾-inch crushed gravel over a non-woven geotextile. A pre-cast concrete and steel vault in the north-central portion of the lot contains a groundwater monitoring well monument (B-9) installed by GeoEngineers in 2017. A fire hydrant is located near the northeast corner along 63<sup>rd</sup> Avenue NE. The District has material stored to the north, east, and south of the gravel pad. We observed standing water throughout the lot during a site visit on 14 February 2023 following previous heavy rain, but it drained relatively quickly.

The line crew training area to the northeast is relatively level and mostly bare ground, although some areas have been mantled with hog fuel. The area is used for excavator training, pole and line setting, and equipment operator training. We observed isolated puddles in high vehicle traffic areas following heavy rain.

It should be noted that almost the entire Special Use Permit area has been disturbed by previous grading activity. Underground utilities have been installed throughout the site, including in the open field where the solar array will be moved and also along the south, east, and north perimeter of the area east of 63<sup>rd</sup> Avenue NE where the new road is planned. These include water, power, and fiber optic cabling. Consequently, disturbance of the upper soil horizon has occurred and fill material is present as well.

# Subsurface Conditions

# Local Geologic Conditions

We assessed the geologic setting of site and the surrounding vicinity by reviewing the *Geologic Map of the Arlington West 7.5 Minute Quadrangle, Snohomish County, Washington* (US Geological Survey, Map MF-1740, 1985). The published geologic mapping indicates the site is underlain by Vashon Recessional Outwash, Marysville Sand Member (Qvrm). The Marysville Sand is described as mostly well-drained, stratified to massive outwash sand, some fine gravel, and some areas of silt and clay. The sediments were deposited by meltwater flowing south from the stagnating and receding Vashon glacier. The outwash is reported to have a minimum thickness of about 65 feet. Subsurface conditions disclosed by the explorations advanced by ZGA and others are consistent with the published mapping. ZGA's explorations disclosed recent fill material above the native soils.



# Soil Conditions

The soil descriptions presented below have been generalized for ease of report interpretation. Please refer to the exploration logs for detailed soil descriptions at the exploration locations. Variations in subsurface conditions may exist between the exploration locations and the nature and extent of variations between the explorations may not become evident until additional explorations are completed or until construction. Undocumented fill material is present and it should be recognized that the nature of undocumented fill material is such that its composition and depth may vary over relatively short distances. Subsurface conditions at specific locations are summarized below.

Our understanding of subsurface conditions is based upon observation of eleven test pits and one hand boring. In addition, we reviewed the logs of borings and test pits completed by GeoEngineers through most of the site and explorations recently completed by ZGA at the Crosswind substation site. Approximate exploration locations, as well as pertinent surface features, are shown on Figure 1. Soil conditions are summarized below.

# Fill

With the exception of test pit TP-7, we did not observe fill material in the explorations completed in the field at the western side of the site. However, we did observe fill in all the explorations completed along the planned access road east of 63<sup>rd</sup> Avenue NE. The fill observed at the TP-7 location extended about 1.5 feet below ground surface (bgs) and consisted of woody debris with a maximum dimension of about 12 inches as well as glass and other deleterious debris. The fill material in the eastern portion of the site contained much more woody debris in addition to metal pipe, glass, and solid waste and extended to depths ranging from about 1 to 3.5 feet bgs. Please note that the nature of undocumented fill is such that its composition and thickness can vary over relatively short distances.

We submitted twelve samples of the fill material to an analytical laboratory to test for the presence of asbestos. The test results were negative.

# <u>Topsoil</u>

We observed about 1 to 1.5 feet of loose, moist, red-brown, silty sand and sandy silt with fine organic material and fine to medium roots and roots hairs at the locations of the test pits completed west of 63<sup>rd</sup> Avenue NE. We have interpreted this material as topsoil. The area east of 63<sup>rd</sup> Avenue NE has been graded in order to prepare the existing pad where the Crosswind substation will be located and along the southern, eastern, and northern perimeter of the site where underground fiber optic utilities have been installed. We observed some relic topsoil between about 1 and 2 feet in depth below some fill material at the hand auger HA-1 location. We did not observe topsoil at the locations of the other explorations in this portion of the site.



# **Recessional Outwash**

The test pits and explorations disclosed that the native recessional outwash soils consisted of loose to dense sand with gravel and a low fines content (the soil fraction passing the US No. 200 sieve). The soils above the water table were generally in a moist condition. The test pits were terminated at depths of approximately 6 to 10.5 feet. Mild to moderate caving with no groundwater seepage was observed in the test pits completed west of 63<sup>rd</sup> Avenue NE, while we observed moderate caving with rapid groundwater seepage as shallow as about 5 feet at the locations of test pits to the east.

# Groundwater

We did not observe groundwater seepage while excavating the test pits located west of 63<sup>rd</sup> Avenue NE. The soil was moist to depths of about 10.5 fee. East of 63<sup>rd</sup> Avenue NE, we observed groundwater seepage at depths of approximately 5 to 8.5 feet while excavating the test pits and the hand auger boring.

Our recent groundwater observations, including a recent measurement made in boring GEB-9 at the Crosswind substation site, are summarized in the table below. It should be noted that groundwater conditions will likely vary seasonally and in response to precipitation events, land use, and other factors. ZGA is currently monitoring groundwater and will forward results in memorandum format on a quarterly basis.

Table 1: Recent Groundwater Observations			
Exploration	Approximate Groundwater	<b>Observation Date</b>	
	Depth/Elevation (feet)		
HA-1	5.5 / 129.5	4.25.23	
TP-1 through TP-8	Not observed	4.24.23	
TP-9	5.5 / 129.5	4.25.23	
TP-10	5 / 131	4.25.23	
TP-11	8 / 128	4.25.23	
GEB-9	7.2 / 129.7	3.29.23	

# CONCLUSIONS AND RECOMMENDATIONS

# **General Geotechnical Considerations**

Based on information gathered during the field exploration, laboratory testing, and analysis, we conclude that construction of the proposed improvements is feasible from the geotechnical perspective provided that the recommendations presented herein are followed during design and construction. Selected aspects of the site conditions that should be considered during design and construction are summarized below.

ZipperGeo Geoprofessional Consultant

- The native recessional outwash soils are generally favorable from the site grading and shallow foundation support perspectives. Selective removal of the existing shallow organic topsoil, disturbed native soils, or undocumented fill material from below foundations is recommended.
- Re-use of the existing non-organic native soil during grading will be feasible provided that the soil
  moisture content can be adequately controlled prior to compaction. The native recessional
  outwash likely to be encountered during grading has a relatively low fines content and may be
  considered moderately moisture-sensitive relative to grading.
- We anticipate that deeper excavations for vaults and conduits may encounter groundwater during the wetter time of year, possibly necessitating dewatering.
- The granular nature of the shallow native recessional outwash soils is favorable from the stormwater infiltration, although it appears that the likely relatively high infiltration rate will preclude relying on the shallow native soils for treatment purposes unless they are amended.
- The non-organic native soils are favorable for pavement support. Pavement longevity will be improved by removing shallow organic soils prior to grading paved areas.
- Based on our analyses, we estimate total settlement resultant from seismically-induced liquefaction of approximately 1 to 3 inches. We estimate differential seismic settlement of approximately ½ to 1½ inches over a horizontal distance of 40 feet. We anticipate that this degree of potential settlement can be adequately accommodated by the new solar array foundations.

Geotechnical engineering recommendations for site grading, drainage, foundations, and other geotechnically-related aspects of the project are presented in the following sections. The recommendations contained in this report are based upon the results of and the field exploration, laboratory testing, engineering analyses, review of reports by others, and our current understanding of the proposed project design. ASTM testing methods and WSDOT specifications co cited herein refer to the current manual published by the American Society for Testing & Materials and the current edition of the WSDOT *Standard Specifications for Road, Bridge, and Municipal Construction* (Publication M41-10).

# Regulated Geologic Hazard Areas

Part V of Chapter 20.93.600 of the Arlington Municipal Code (AMC) defines regulated geologic hazard areas as follows:

"Geologic hazard areas" means lands or areas susceptible to erosion, sliding, earthquakes, liquefaction, or other geological events.



# Landslide Hazard Areas

"Landslide hazard areas" include areas subject to severe risk of landslide based on a combination of geologic, topographic, and hydrologic factors. Landslide hazard include any of the following:

- (A) Areas characterized by slopes greater than fifteen percent and impermeable soils (typically silt and clay) frequently interbedded with permeable granular soils (predominantly sand and gravel) or impermeable soils overlain with permeable soils or springs or groundwater seepage; Low Hazard. Areas with slopes of less than 15 percent.
- (B) Any area that has exhibited movement during the Holocene epoch (from ten thousand years ago to present) or which is underlain by mass wastage debris of that epoch;
- (C) Any area potentially unstable due to rapid stream incision, stream bank erosion or undercutting by wave action;
- (D) Any area located on an alluvial fan presently subject to or potentially subject to inundation by debris flows or deposition of stream-transported sediments;
- (E) Any area with a slope of thirty-three percent or greater and a vertical relief of ten or more feet except areas composed of consolidated rock;
- (F) Any area with slope defined by the United States Department of Agriculture Soil Conservation Service as having a severe limitation for building site development; and,
- (G) Any shoreline designated or mapped as class U, UOS, or URS by the Department of Ecology Coastal Zone Atlas.

As described above, the project site is essentially level and lacks significant slopes, including slopes 15 percent or steeper. It is our opinion that the site presents a low landslide hazard per the AMC definition.

# Seismic Hazard Areas

<u>Seismic Design Considerations</u>: The seismic performance of the proposed site improvements was evaluated in accordance with the 2018 International Building Code (IBC). The seismic basis of design for the 2018 IBC, which refers to the American Society of Civil Engineers (ASCE) 7-16, is a risk-targeted maximum considered earthquake (MCE<sub>R</sub>), which represents an earthquake with a 2 percent probability of exceedance in 50 years (2,475-year return period).

<u>Ground Fault Rupture</u>: Based on review of the United States Geological Survey *Quaternary Fault and Fold Database of the United States* the nearest fault to the site is the South Whidbey Island Fault Zone mapped about 17 miles south-southwest of the site. Based on the mapped location of the fault relative to the site, it is our opinion that the risk associated with fault surface rupture at the site is low.

<u>Liquefaction</u>: Liquefaction is a phenomenon wherein saturated cohesionless soils build up excess pore water pressures during earthquake loading. Liquefaction typically occurs in loose soils, but may occur in denser soils if the ground shaking is sufficiently strong. ZGA completed a liquefaction analysis in general accordance with the 2018 IBC and ASCE 7-16. Specifically, our analysis used the following primary seismic

Crosswind Substation - DRAFT Project No. 2679.01 1 June 2023 ground motion parameters.



- A Modified Peak Ground Acceleration (PGA<sub>M</sub>) of 0.52g based on Site Class D, per Section 11.8.3 of ASCE 7-16 (Site Class modification to MCE<sub>G</sub> without regard to liquefaction in accordance with Sections 11.4.8 and 20.3.1 of ASCE 7-16).
- A Geometric Mean Magnitude of 7.03 based on 2014 USGS National Seismic Hazard Mapping Project deaggregation data for a seismic event with a 2% probability of exceedance in 50 years (2,475-year return period).

Our liquefaction analysis was completed using the computer program CLiq (Version 3.5.2.10) developed by GeoLogismiki. Our analysis was based on CPT-01 completed to a depth of about 60 feet below existing grade within the proposed development area and assumed a conservative groundwater depth of 2 feet during the design earthquake. The approximate exploration location is shown on the enclosed *Site and Exploration Plan, Figure 1*. Based on our analysis, a generally non-liquefiable crust of material exists in the upper 15 feet of the site. Below this crust, portions of the Marysville Sand Member have a moderate to high liquefaction potential during the design earthquake down to the full depth of the CPT exploration.

<u>Liquefaction Settlement</u>: The site is mantled by a generally dense and non-liquefiable crust on the order of 15 feet thick. As such, liquefaction-indicated settlements observed at the surface will initiate from potentially liquefiable layers present below the non-liquefiable crust. Research and case histories have shown that the expression of liquefaction-induced settlement at the ground surface is a function of the depth of the liquefiable layers, with deeper liquefiable layers contributing less to ground surface settlement than similar thickness shallow liquefiable layers (Cetin et al., 2009). Cetin proposed use of a "depth weighting factor" (DF<sub>i</sub>) that reduces the impact of deep liquefiable layers on the estimated surface settlement. This factor is included in the CLiq program and was used in our settlement analysis.

Based on our analyses, we estimate a total seismic settlement of approximately 1 to 3 inches. We estimate a differential seismic settlement of approximately ½ to 1½ inches over a horizontal distance of 40 feet. Appendix C contains selected seismic analysis data sheets.

<u>Lateral Spread</u>: Lateral spreading is a phenomenon in which soil deposits which underlie a site can experience significant lateral displacements associated with the reduction in soil strength caused by soil liquefaction. This phenomenon tends to occur most commonly at sites where the soil deposits can flow toward a "free-face", such as a water body. Given the relatively level nature of the site, lack of a free-face condition, and 15-foot-thick non-liquefiable crust, it is our opinion that the potential for distress at the site from lateral spreading is low.

<u>Additional Liquefaction Analysis</u>: The District retained Hart Crowser to complete a liquefaction analysis at the Microgrid site, and their conclusions and recommendations are summarized in the report titled *Geotechnical Engineering Design Study, North County Development, Arlington, Washington* (Project No.



19583-00, dated 20 January 2022). Hart Crowser's analysis was based on subsurface information provided in the GeoEngineers reports described earlier. Similar to the results of ZGA analysis, Hart Crowser concluded that liquefaction-induced settlement on the order of 2 to 4 inches resultant from the modeled maximum credible seismic event was likely, and recommended designing project structures for 2 inches of differential settlement over a distance of 30 feet.

Table 2: IBC Seismic Design Criteria		
Parameter	Value	
2018 International Building Code Site Classification (IBC) <sup>1</sup>	Site Class F <sup>2,3</sup>	
Site Latitude/Longitude	48.1560 /-122.1422	
Spectral Short-Period Acceleration, Ss	1.050g	
Spectral 1-Second Acceleration, S <sub>1</sub>	0.375g	
Site Coefficient for a Short Period, F <sub>A</sub>	1.080	
Site Coefficient for a 1-Second Period, $F_{\rm V}$	See ASCE Section 11.4.8	
Spectral Acceleration for a 0.2-Second Period, $S_{MS}$	1.134g	
Spectral Acceleration for a 1-Second Period, $S_{M1}$	See ASCE Section 11.4.8	
Design Short-Period Spectral Acceleration, S <sub>DS</sub>	0.756g	
Design 1-Second Spectral Acceleration, S <sub>D1</sub>	See ASCE Section 11.4.8	

1. IBC Site Class is based on the average characteristics of the upper 100 feet of the subsurface profile.

2. CPT-01 completed by ZGA for this study extended to a maximum depth of about 60 feet below grade. Therefore ZGA reviewed logs for CPT-1 and CPT-2 completed by GeoEngineers in 2017 (including shear wave velocity test results) about 2,000 and 1,200 feet west of the site, respectively, to determine IBC site class with and without regard to liquefaction.

3. Per the *2018 International Building Code* and *ASCE 7-16*, Chapter 20, any profile containing soils vulnerable to potential failure or collapse under seismic loading such as liquefiable soils.

# **IBC Seismic Design Parameters**

Per the 2018 IBC seismic design procedures and ASCE 7-16, the presence of liquefiable soils requires a Site Class definition of F. However, through reference to Sections 11.4.8 and 20.3.1 of ASCE 7-16, the 2018 IBC allows site coefficients  $F_a$  and  $F_v$  to be determined assuming that liquefaction does not occur for structures with fundamental periods of vibration less than 0.5 seconds. Based on the results of the field evaluation, Site Class D may be used to determine the values of  $F_a$  and  $F_v$  in accordance with Sections 11.4.8 and 20.3.1 of ASCE 7-16. If exceptions for Site Class D presented in Section 11.4.8 of ASCE 7-16 do not apply, a ground motion hazard analysis may be required. Site Class D describes soils that are considered stiff with a shear wave velocity between 600 and 1,200 feet per second, average Standard Penetration Test values between 15 and 50, and an undrained shear strength between 1,000 and 2,000 psf.

# **Engineering Soil Units**

For purposes of describing soil conditions observed at the exploration locations and for reference in other sections of this report, soils with similar engineering characteristics were grouped together into

ZipperGeo

Engineering Stratigraphic Units or ESUs. The following paragraphs provide our interpretation of ESUs encountered at the exploration locations. ESUs are described in a top down stratigraphic sequence described in the logs. The reader is referred to the logs attached in Appendix A for information regarding subsurface conditions.

<u>ESU 1 – Topsoil:</u> Soils located in the western relocated solar area between about 1 and 1.5 feet deep are interpreted to be topsoil characterized as loose, silty sand and sandy silt with trace gravel and a high organic content. Engineering properties of ESU 1 soils are characterized as low strength and compressible materials.

<u>ESU 2 –Undocumented fill/disturbed native soil:</u> We observed soils interpreted to be undocumented fill at one test pit location (TP-7) west of 63<sup>rd</sup> Avenue NE to a depth of about 1.5 feet below existing site grade. Along the rail line at the eastern area of the site, ESU-2 soils were observed from about 1 to 1.5 feet bgs. ESU 2 fill soils generally consisted of loose silt, sand, gravel, cobbles, and deleterious material such as glass, metal pipes, branches, and plastic debris. The disturbed native soils were of similar density and composition but lacked the deleterious debris and are related to previous site grading. Engineering properties of ESU 2 soils are characterized as low strength and compressible materials. Please note that while we only observed fill material at the test pit TP-7 location in the western portion of the site, additional fill material is present in the form of backfilled underground utility trenches across the entire site.

<u>ESU 3 – Loose to medium dense recessional outwash (Qvrm – Marysville Sand Member)</u>: Soils interpreted to be shallow loose to medium dense recessional outwash soils were observed at most of the exploration locations. These loose to medium dense materials tend to be moderately weathered and extend from about 1.5 feet to 4 feet bgs. Engineering properties of ESU 3 soils are characterized as low to moderate strength low compressibility materials.

<u>ESU 4 – Medium dense to dense recessional outwash (Qvrm – Marysville Sand Member)</u>: Soils interpreted to be medium dense recessional outwash soils were generally observed at depths below about 4 feet. Engineering properties of ESU 4 soils are characterized as moderate to high strength low compressibility materials. ESU 4 soils include structural fill compacted to at least 95 percent density per ASTM D 1557.

# Earthwork

The following sections present recommendations for site preparation, subgrade preparation, and placement of engineered fills on the project. The recommendations presented in this report for design and construction of embankments, foundations, pavements, and slabs are contingent upon following the recommendations outlined in this section.

Earthwork on the project should be observed and evaluated by a ZGA representative. Evaluation of earthwork should include observation and testing of structural fill, subgrade preparation, foundation bearing soils, deep foundations, and subsurface drainage installations.



<u>Stripping:</u> In preparation for grading, we recommend removal of any existing surficial vegetation, root mass, organic topsoil, and deleterious debris if present. These materials should be wasted from the substation footprint. We also recommend selective removal of existing undocumented fill material or disturbed native soils containing substantial organics or deleterious debris and any relic organic topsoil from below solar array foundations, pavements, or other settlement-sensitive project improvements.

Variation in the undocumented fill and disturbed native soil depth and composition should be expected. These materials should be evaluated during construction and removed as necessary under the observation of a ZGA representative. Our representative will identify unsuitable materials that should be removed and possibly some that may be re-used as structural fill. Soil with no more than about 3 percent organic material and lacking deleterious material may generally be left in place. The resultant excavations should be backfilled in accordance with the subsequent recommendations for structural fill placement and compaction. The amount of soil removed during the stripping process may be reduced if root rakes are employed. Root rakes allow segregation of roots from the surrounding mineral soil, and can be beneficial in terms of reducing the amount of soil likely removed during stripping.

<u>Site Preparation and Grading Scheduling:</u> Most of the native soils likely to be exposed during grading consist of sand and gravel with a variable fines content. It will be feasible from the geotechnical perspective to grade these soils under a relatively wide weather band, although even with favorable granular soils it may be difficult or impossible to grade the site during very wet weather. If this concerns the District, we recommend that site preparation and grading take place in the drier summer and early fall months if possible. Completion of site preparation and grading under drier site and weather conditions will reduce the potential for disturbance of moisture-sensitive soils that may be disclosed during grading and the need to replace disturbed soils with imported fill material. Completing the work during the drier summer and early fall months will also allow the grading to coincide with the seasonal low groundwater condition and this would reduce the extent of construction dewatering.

# **Structural Fill Placement and Compaction**

A grading plan was not available at the time this report was prepared. However, we anticipate that substantial grading will not be required in association with construction of the relocated solar array, new parking/materials storage, perimeter road, and stormwater management elements. All fill material should be placed in accordance with the recommendations herein for structural fill. Prior to placement, the surfaces to receive structural fill should be observed by a ZGA representative in order to verify that at least medium dense properly prepared fill or native soil is present. In the event that soft or loose soils are present at the subgrade elevation, they should be compacted to a firm and non-yielding condition and to at least 95 percent of the modified Proctor maximum dry density (ASTM D 1557) prior to placing structural fill. In the event that the soils cannot be adequately compacted, they should be moisture condition as necessary or removed as necessary and replaced with other granular fill material at a moisture content that allows its compaction to the recommended density.



The suitability of soils for use as structural fill depends primarily on the gradation and moisture content of the soil when it is placed. As the amount of fines (that soil fraction passing the US No. 200 sieve) increases, soil becomes increasingly sensitive to small changes in moisture content and adequate compaction becomes more difficult, or impossible, to achieve. Generally, soils containing more than about 5 percent fines by weight (based on that soil fraction passing the US No. 4 sieve) cannot be compacted to a firm, non-yielding condition when the moisture content is more than a few percent from optimum. The optimum moisture content is that which yields the greatest soil density under a given compactive effort.

<u>Re-use of On-site Soils</u>: Soil expected to be encountered in excavations include predominantly native soil typically consisting of sand and gravel with a variable fines content. The fines content of soil samples that we tested (as deep as about 12 feet and likely to be encountered in excavations) ranged at the western portion of the site from about 2 to 11 percent with an outlier at TP-8 of 23 percent and, in the eastern portion of the site, from about 1 to 18 percent. Please note that the samples with the higher fines contents were the shallow weathered soils. We observed the highest fines content in the very shallow soils; the fines content generally decreased with depth. Using the shallow soils with the higher fines content as structural fill during wet weather could be difficult due to the soils' increased moisture sensitivity.

Table 3: Recommended Gradation of Imported Structural Fill			
US Standard Sieve Size	Percent Passing by Dry Weight Basis		
2 inch	100		
½ inch	56 - 100		
¼ inch	40 - 78		
No. 10	22 - 57		
No. 40	8 - 32		
No. 200	< 5		

<u>Imported Structural Fill</u>: We recommend that structural fill consist of well-graded sand and gravel with a low fines content. An example gradation is shown in the table below.

This material may be considered slightly to moderately moisture-sensitive relative to placement and compaction. A means of reducing the moisture sensitivity of the imported fill would be to base the fines content to less than 5 percent based on the soil fraction passing the ½ inch sieve. It would be feasible to use other granular soils with a higher fines content as structural fill, but it should be recognized that soils with a higher fines content will be more moisture-sensitive and this may limit their use during wet weather or wet site conditions. Another advantage of using granular fill with a relatively low fines content is that it will drain better than fill with a higher fines content. The use of other fill types should be reviewed and approved by ZGA prior to their use on site.



<u>Compaction Recommendations</u>: Structural fill should be placed in horizontal lifts and compacted to a firm and non-yielding condition using equipment and procedures that will produce the recommended moisture content and densities throughout the fill. Fill lifts should generally not exceed 10 inches in loose thickness, although the nature of the compaction equipment in use and its effectiveness will influence functional fill lift thicknesses. Recommended compaction criteria for structural fill materials, including trench backfill, are as follows:

Table 4: Recommended Soil Compaction Levels			
Location	Minimum Percent Compaction*		
Below foundations and slabs	95		
Below pavements and concrete hardscapes	95		
General fill embankments	90 – 95 (refer to report text)		
Utility trenches, foundation, and slab backfill	95		
* ASTM D 1557 Modified Proctor Maximum Dry Density			

Earthwork may be difficult or impossible during periods of elevated soil moisture and wet weather. If soils are stockpiled for future use and wet weather is anticipated, the stockpile should be protected with plastic sheeting that is securely anchored.

Subgrade soils that become disturbed due to elevated moisture conditions should be overexcavated to expose firm, non-yielding, non-organic soils and backfilled with compacted structural fill. We recommend that the earthwork portion of this project be completed during extended periods of dry weather if possible. If earthwork is completed during the wet season (typically November through June) it will be necessary to take extra precautionary measures to protect subgrade soils. Wet season earthwork may require additional mitigative measures beyond that which would be expected during the drier summer and fall months. This could include diversion of surface runoff around exposed soils and draining of ponded water. Once subgrades are established, it will be necessary to protect the exposed subgrade soils from construction traffic during wet weather. Placing quarry spalls or crushed rock ballast over these areas would further protect the soils from construction traffic.

If earthwork takes place during freezing conditions, we recommend allowing the exposed subgrade to thaw and then recompacting the subgrade prior to placing subsequent lifts of engineered fill. Frozen soil should not be used as structural fill.

We recommend that a ZGA representative be present during the construction phase of the project to observe earthwork operations and to perform necessary tests and observations during subgrade preparation, placement and compaction of structural fill, backfilling of excavations, and prior to construction of foundations.

ZipperGeo

<u>Drainage:</u> Positive drainage should be provided during construction and maintained throughout the life of the project. Uncontrolled movement of water into utility trenches or foundation excavations during construction should be prevented.

<u>Excavation Quantities</u>: It has been our experience that grading calculations need to accommodate a "shrink or swell" factor when comparing in-place soil volumes to truck volumes. We recommend considering that the in-place volume of soil removed from excavations will increase by approximately 25 to 40 percent when measured on a loose cubic yards basis (truck yards). Likewise, loose truck yards delivered to the site will shrink on the order of 25 to 30 percent when compared to the in-place compacted volume of the soil. Truck yards are also subject to other discrepancies when correlating to bank yards, including "rounding errors" that can be significant.

# **Utility Installation Recommendations**

Below-grade utilities are expected to include conduits and storm drain piping and structures. We recommend that utility trenching conform to all applicable federal, state, and local regulations, such as OSHA and WISHA, for open excavations. The existing shallow native and fill soils in the substation footprint are generally expected to be adequate for support of utilities.

All trenches should be wide enough to allow for compaction around the haunches of the pipe. If water is encountered in the excavations, it should be removed prior to fill placement. Materials, placement and compaction of utility trench backfill exclusive of CDF should be in accordance with the recommendations presented in the *Structural Fill* section of this report. In our opinion, the initial lift thickness should not exceed 1 foot unless recommended by the manufacturer to protect utilities from damage by compacting equipment. Light, hand operated compaction equipment may be utilized directly above utilities if damage resulting from heavier compaction equipment is of concern.

<u>Dewatering</u>: Groundwater observations and measurements made as of the time that this report was prepared are described in Table 1 on Page 5. In summary, we did not observe groundwater while excavating test pits in the future relocated solar array area in the western portion of the site, although we did observe groundwater seepage at depths of about 5 to 8 feet in explorations in the eastern portion of the site. ZGA is continuing to monitoring groundwater at the Microgrid property and quarterly summaries will be provided to the District.

Depending upon the time of year that the work takes place and the depth of the utilities, groundwater seepage could be expected in excavations and certainly during the wetter time of year. Seepage could be heavy enough to require temporary dewatering measures and flattening the sidewalls of excavations to reduce the risk of caving. The contractor should be prepared to pump water from excavations into a nearby storm sewer or Baker tank. We recommend that dewatering effectively lower the water table at least 2 feet below the bottoms of excavations until they are backfilled.

<u>Temporary Excavation Slopes:</u> We recommend that utility trenching, installation, and backfilling conform to all applicable Federal, State, and local regulations such as WISHA and OSHA regulations for open

ZipperGeo

excavations. In order to maintain the function of any existing utilities that may be located near excavations, we recommend that temporary excavations not encroach upon the bearing splay of existing utilities, foundations, or slabs. The bearing splay of structures and utilities should be considered to begin at the edge of the utility, foundation, or slab and extend downward at a 1.5H:1V (Horizontal:Vertical) slope under fully drained conditions. Much shallower temporary slope inclinations will be required under saturated soil conditions. If, due to space constraints, an open excavation cannot be completed without encroaching on a utility, we recommend shoring the new utility excavation with a slip box or other suitable means that provide for protection of workers and that maintain excavation sidewall integrity to the depth of the excavation.

Temporary slope stability is a function of many factors, including the following:

- The presence and abundance of groundwater;
- The type and density of the various soil strata;
- The depth of cut;
- Surcharge loadings adjacent to the excavation;
- The length of time the excavation remains open.

It is difficult to pre-establish a safe and "maintenance-free" temporary cut slope angle. Therefore, it should be the responsibility of the contractor to maintain safe slope configurations since the contractor is continuously at the job site, able to observe the nature and condition of the cut slopes, and able to monitor the subsurface materials and groundwater conditions encountered. It may be necessary to drape temporary slopes with plastic or to otherwise protect the slopes from the elements and minimize sloughing and erosion. We do not recommend vertical slopes or cuts deeper than 4 feet if worker access is necessary. The cuts should be adequately sloped or supported to prevent injury to personnel from local sloughing and spalling. The excavation should conform to applicable Federal, State, and local regulations.

Based upon our review of WAC Chapter 296-155-66401 (Appendix A – Soil Classification), we have interpreted the soils disclosed by the explorations and likely to be present in most excavations as consistent with the Type C definition. The contractor should be responsible for determining soil types in all excavations at the time of construction and should be prepared to adequately shore or slope all excavations. Please note that the shallow granular soils have a low fines content and that unsupported excavation sidewalls in these soils may slough or cave readily.

# **Solar Array Foundation Recommendations**

Based upon our review of RBI Solar design documents associated with the existing solar array (dated 18 February 2019) and provided by the District, it appears that the relocated solar array components may be



supported by either cast-in-place drilled pier foundations, conventional shallow column foundations, or by small driven C-piles or H-piles. Our conclusions and recommendations regarding foundations for the relocated array are summarized below.

# Drilled Pier Foundations

<u>Drilled Pier End Bearing and Settlement</u>: The existing array design called for 18-inch diameter drilled piers installed to a depth of 6 feet. Based on conditions disclosed by the GeoEngineers and ZGA explorations completed in the relocated solar array location, we recommend using an allowable end bearing value of 9 kips per square foot (ksf) for drilled piers installed into the dense recessional outwash soils. This value incorporates a factor of safety of three and may be increased by one third for short-term transient loading. Foundation settlement is expected to be less than one-half inch.

<u>Drilled Pier Uplift Capacity</u>: Uplift forces acting on the drilled piers may be counteracted by the weight of the piers and skin friction between the piers and the surrounding soil. An allowable uplift capacity of 2.8 tons due to skin friction may be considered. This value incorporates a factor of safety of 2.5.

<u>Open Shaft Construction Considerations</u>: Given the soil conditions encountered at the explorations locations, we anticipate that construction of the shafts can be accomplished with standard drilling equipment. We observed undisturbed native soils, as well as some likely disturbed native soils and some undocumented fill material to depths of about 1.5 feet below existing grade. The contractor should be prepared to deal with the presence of cobbles, concrete clasts, and wood over the drilled depth interval. In the event that obstructions cannot be removed, it will be necessary to excavate them and then backfill the excavation with either compacted structural fill or Controlled Density Fill (CDF) prior to attempting to re-drill the shafts.

We anticipate that sidewall caving may occur while drilling the granular soils, some of which have a relatively low fines content. We recommend that the contractor be prepared to case the drilled shaft boreholes to reduce sidewall sloughing. We recommend that the contractor be required to have on site sufficient material to case the entire drilled depth of the drilled pier foundations. The drilling contractor should be prepared to clean out the bottom of the shafts if loose soil is observed or suspected. We recommend that the drilling contractor have a cleanout bucket on site to remove loose soils from the bottom of the borings.

<u>Concrete Placement</u>: We recommend that the foundation concrete be tremied from the bottom of the hole to displace water and to reduce the risk of contaminating or segregating the concrete mix should any accumulate in the shafts. A minimum 5-foot head of concrete should be maintained above the tremie. The *Drilled Shaft Manual* published by the Federal Highway Administration recommends that concrete be placed by tremie methods if more than 3 inches of water has accumulated in the excavation. Otherwise, if the shafts are dry or nearly dry, concrete may be placed via conventional chute delivery.


We recommend that a ZGA representative observe construction of the drilled pier foundations in order to verify that the bearing conditions are consistent with those described in this report.

### Conventional Shallow Foundations

The existing array design called for 5.3-foot square isolated cast-in-place spread foundations to be constructed a depth of 1.5 feet. Our shallow foundation recommendations are summarized below.

<u>Net allowable bearing pressure:</u> 3,500 psf for ESU 4 soils. This value incorporates a factor of safety of 3. A one-third increase may be applied for short-term wind or seismic loading.

### Minimum base dimension for standard column foundation per previous design: 5.3 feet

Minimum embedment for frost protection: 18 inches

Approximate total settlement: 1 inch

Estimate differential settlement: One half of total settlement

<u>Ultimate passive resistance</u>: 480 pcf. This value assumes that foundations are backfilled with native sand and gravel compacted to 95 percent density and does not include a factor of safety. Neglect the upper 18 inches of embedment when calculating passive resistance.

<u>Ultimate coefficient of base friction:</u> 0.55. This value assumes the foundations are formed above compacted CSBC and does not include a factor of safety.

<u>Shallow Foundation Construction Considerations</u>: The base of all foundation excavations should be free of water, loose soil, or debris prior to placing concrete, and loose soil disturbed during excavation should be compacted as recommended in this report. Concrete should be placed soon after excavating and form and reinforcing installation to reduce bearing soil disturbance. Should the bearing subgrade become excessively disturbed or frozen, the affected material should be removed prior to placing concrete. We recommend that a ZGA representative observe foundation subgrade conditions prior to form and reinforcing steel placement.

### Driven Pile Foundation Considerations

We understand that RBI Solar installed six test piles (five C8X3 piles and one W6X9 piles) during the existing solar array design process. The test pile program included the use of a proprietary hammer system, and the tests indicated that adequate capacities could be achieved by installing the piles at a maximum depth of 8 feet below grade. Soil conditions at the test piles locations are similar to those observed in the area where the relocated solar array will be installed, and we anticipate that the use of

Crosswind Substation - DRAFT Project No. 2679.01 1 June 2023 driven piles installed as described in the RBI Solar design documentation will be adequate at the new array location as well.

### **Stormwater Infiltration Feasibility**

Construction of the new parking/materials storage area north of the relocated solar array and the new perimeter access road east of 63<sup>rd</sup> Avenue NE will introduce impervious surfaces, and the stormwater runoff will need to be accommodated by new stormwater management features. The site is underlain by permeable native granular soil and is characterized by a variable depth seasonal groundwater condition. Conclusions regarding stormwater infiltration feasibility can be drawn from subsurface conditions disclosed by the subsurface explorations, groundwater observations, and laboratory testing completed to date.

We understand that stormwater management improvements will be designed in accordance with the Washington State Department of Ecology 2019 *Stormwater Management Manual for Western Washington (Manual)*. We collected representative samples of shallow soils and completed mechanical grain size tests as part of assessing the soils' saturated hydraulic conductivity, as summarized below.

### Saturated Hydraulic Conductivity

The *Manual* allows a determination of soil saturated hydraulic conductivity to be estimated based on grain size distribution characteristics in accordance with the following formula:

Log10 ( $K_{sat, initial}$ ) = -1.57 + 1.9 $D_{10}$  + 0.015 $D_{60}$  – 0.013 $D_{90}$  -2.08 $f_{fines}$  where:

 $K_{sat, initial}$  = initial saturated hydraulic conductivity in centimeters/second prior to the application of correction factors

 $D_{10}$  = grain size diameter (mm) for which 10 percent of the sample by weight is finer

 $D_{60}$  = grain size diameter (mm) for which 60 percent of the sample by weight is finer

 $D_{90}$  = grain size diameter (mm) for which 90 percent of the sample by weight is finer

 $f_{\text{fines}}$  = fraction of the sample by weight that passes the US No. 200 sieve.

The calculated hydraulic conductivity values for representative soils that we tested are listed in the table below. Grain size distribution curves for the samples are presented in Appendix B.



Table 5: Saturated Hydraulic Conductivity Summary									
Exploration /	Approximate Sample	Unfactored Saturated	Factored Saturated						
Sample	Depth	Hydraulic Conductivity	Hydraulic Conductivity						
	(feet)	(inches per hour)	(inches per hour)						
Location: West of 63 <sup>rd</sup> Avenue NE									
TP-1 / S-3	3.5	63.4	9.4						
TP-2 / S-3	3.0	80.7	12						
TP-4 / S-2	1.5	170.9	25.4						
TP-5 / S-2	2.5	23	3.4						
TP-6 / S-2	2.5	30.2	4.5						
TP-7 / S-2	3.0	14.7	2.2						
TP-8 / S-2	2.0	14.6	2.2						
TP-8 / S-3	3.0	69.4	10.3						
	Locatio	on: East of 63 <sup>rd</sup> Avenue NE							
HA-1 / S-2	1.5	18	2.7						
HA-1 / S-4	3.5	34.5	5.1						
TP-9 / S-2	3.0	42.7	6.3						
TP-10 / S-2	2.5	43.8	6.5						
TP-10 / S-3	5.0	151.9	22.6						
TP-11 / S-1	0.5	20.2	3						
TP-11 / S-3	8.0	104.3	15.5						

### Design Saturated Hydraulic Conductivity Rate

The *Manual* requires applying correction factors to the baseline (initial) saturated hydraulic conductivity rate. Table 3.3.1 *Correction Factors to be Used with In-Situ Saturated Hydraulic Conductivity Measurements to Estimate Design Rates* of the *Manual* calls for 40 percent reduction of the baseline rate determined via the grain size method ( $CF_T$ ). Table 3.3.1 also requires applying correction factors for site variability and number of locations tested ( $CF_v$ ) and the degree of influent control to prevent siltation and bio-buildup ( $CF_M$ ). Based upon the observed site conditions, testing results, and our experience with projects of a similar nature, we applied values of 0.33, 0.5, and 0.9 for  $CF_v$ ,  $CF_T$ , and  $CF_M$ , respectively. Factored rates are included in Table 5 above.

We anticipate that runoff from the new road east of 63<sup>rd</sup> Avenue NE may be accommodated by relatively shallow infiltration features, such as bioswales or trenches. Based upon this condition, we recommend applying an allowable long-term infiltration rate of 5.3 inches/hour for facilities constructed east of 63<sup>rd</sup> Avenue NE. We recommend applying an allowable long-term infiltration rate of 4.7 inches/hour for facilities west of 63<sup>rd</sup> Avenue NE.



#### In Situ Stormwater Treatment

To assess the feasibility of using shallow native soils to provide stormwater runoff treatment, five shallow soil samples were tested for Cation Exchange Capacity (CEC) as well as organic content. The *Manual* requires that the infiltration receptor soil possess a minimum CEC value of 5 meq/100g of dry soil determined in accordance with the USEPA Method 9081 and an organic content of 1 percent or greater as determined via the ASTM D2974-07 test method in order to provide adequate *in situ* treatment of stormwater. Four of the five samples had CEC values greater than 5 meq/100g; only the sample from test pit TP-10 along the far east side of the site had a lesser value of 3.3 meq/100g. Each of the samples had an organic content exceeding 1 percent. Based on the test results and our observation of shallow soils, it appears that overall shallow soil conditions are favorable for *in situ* treatment provided that some soil amendment is completed in the vicinity of test pit TP-10.

*SSC-4 Soil Infiltration Rate/Drawdown Time* from the *Manual* indicates that the measured (initial/unfactored) soil infiltration should be 9 inches/hour or less for *in situ* treatment to be effective. However, the unfactored infiltration rates we determined exceeded 9 inches/hour. Consequently, it appears that some form of soil amendment of the native soils will be necessary to reduce the soil infiltration rate, or that treatment may be provided by using an imported soil mix that has been demonstrated to meet the *Manual* requirements.

It would be necessary to complete additional laboratory testing of amended site soils in order to determine the type and quantity of amendments necessary for the treated on-site soil to meet the relatively low infiltration rate described in the *Manual* for effective treatment. We can assist the District in this regard if requested. Alternatively, it would be feasible to import ready-made manufactured amended soil rather than attempting to amend the site soils. In the event that imported material is used for treatment purposes, we recommend considering the grain size distribution shown in the table below.

Table 6: Recommended Imported Treatment Fill Gradation				
US Standard Sieve Size	Percent Passing by Dry Weight Basis			
3/8 inch	100			
No. 4	95 - 100			
No. 10	75 - 90			
No. 40	25 - 40			
No. 100	4 - 10			
No. 200	< 5			

In addition to the gradation criteria list in the table above, we recommend that the material have a Coefficient of Uniformity (Cu) =  $D_{60}/D_{10}$  greater than or equal to 4 and a Coefficient of Curve (Cc) =  $(D_{30})^2/(D_{60} \times D_{10})$  greater than or equal to 1 and less than or equal to 3. This material may be amended with compost. Please note that the imported fill gradation criteria are taken from the bioretention mix material described in the WDOE Stormwater Management Manual for Western Washington.



### **Groundwater Considerations**

Groundwater conditions observed while completing the test pits and hand auger boring advanced for this evaluation are presented in Table 1 on Page 5. The reported seasonal high groundwater observations at the site described in GeoEngineers' two-year groundwater monitoring effort undertaken in 2017 and 2018 are summarized in the table below. These observations illustrate that the depth to groundwater increased from east to west during the monitoring period. Our recent observations confirmed this condition.

Table 7: GeoEngineers Reported Historical Seasonal High Groundwater						
Exploration/Well	Reported Seasonal High	Observation	Ground Surface			
	Groundwater Depth/Elevation*	Date	Elevation* (feet)			
	(feet)					
GEB-3	7.2 / 126.7	4.20.28	133.9			
GEB-4	2.6 / 132.0	4.18.18	134.6			
GEB-8	6.1 / 129.9	2.18.18	136.0			
GEB-9	1.0 / 135.2	4.17.18	136.2			
GEB-10	7.5 / 125.5	4.20.18	133			
GEB-11	6.1 / 127.9	4.20.18	134			
*Ground surface elevations reported on North County Community Office survey (9 sheets), by David						
Evans & Associates, Inc., dated 3.22.22.						

The previously observed shallow depth to seasonal high groundwater report by GeoEngineers for borings GEB-4 and GEB-9 east of 63<sup>rd</sup> Avenue NE suggest that a shallow stormwater infiltration feature, such as a bioretention swale, may be required in order to meet the minimum separation distance between the bottom of infiltration BMPs and seasonal high groundwater. Separation as low as 1 foot may be permissible when using bioretention features. Alternatively, some other form of shallow infiltration, such as permeable pavement, may be necessary.

### Flexible Pavement Section Recommendations

Improvement plans include constructing an asphalt-paved access road along the perimeter of the eastern portion of the site as well as constructing paved parking and materials storage to the north of the relocated solar array. When developing our recommendations, we considered that the pavements will be subject to passenger vehicles, typical District service vehicles, and occasional heavy trucks. Our recommended minimum pavement section may be inadequate in the event that the District plans to operate heavily loaded solid-tire forklifts in the new material storage area. If this is the case, please confirm the anticipated equipment to be used in this area and its frequency so that we can evaluate alternative pavement sections. Our recommendations for flexible pavement section are summarized below.



<u>Pavement Life and Maintenance:</u> It should be realized that asphaltic pavements such as hot mix asphalt (HMA) are not maintenance-free. The following pavement sections represent our minimum recommendations for an average level of performance during a 20-year design life; therefore, an average level of maintenance will likely be required. Thicker asphalt, base, and subbase courses would offer better long-term performance, but would cost more initially. Conversely, thinner courses would be more susceptible to "alligator" cracking and other failure modes. As such, pavement design can be considered a compromise between a high initial cost and low maintenance costs versus a low initial cost and higher maintenance costs.

<u>Soil Design Values</u>: Shallow pavement subgrade soils are anticipated to consist of well-compacted sand with a variable fines content and generally low gravel content. This condition may be considered "fair" relative to pavement support. Our analysis assumes the pavement section subgrade will have a minimum California Bearing Ratio (CBR) value of 10.

<u>Recommended Pavement Section</u>: We recommend that the pavement section, at a minimum, consist of 3 inches of asphalt concrete over 3 inches of asphalt-treated base (ATB) over 6 inches (compacted thickness) of crushed surfacing base course (CSBC).

We recommend the following regarding flexible pavement materials and pavement construction.

<u>Subgrade Preparation and Compaction</u>: We anticipate that the pavement subgrade will consist of nonorganic native soil and structural fill that has been prepared in accordance with the recommendations presented in the *Subgrade Preparation* section of this report. All subgrade soils should be compacted in accordance with the recommendations presented in the *Structural Fill* section of this report.

<u>HMA:</u> We recommend that the HMA conform to Section 9-02.1(4) for PG 58-22 or PG 64-22 Performance Graded Asphalt Binder as presented in the WSDOT *Standard Specifications*. We also recommend that the gradation of the HMA aggregate conform to the aggregate gradation control points for ½-inch mixes as presented in Section 9-03.8(6), HMA Proportions of Materials.

<u>Base Course:</u> We recommend that the CSBC conform to Section 9-03.9(3) of the WSDOT *Standard Specifications*.

<u>Compaction and Paving</u>: We recommend compacting the HMA to a minimum of 92 percent of the Rice (theoretical maximum) density. Placement and compaction of HMA should conform to requirements of Section 5-04 of the *Standard Specifications*.

### **Erosion Control**

Construction phase erosion control activities are recommended to include measures intended to reduce erosion and subsequent sediment transport. We recommend that the project incorporate the following erosion and sedimentation control measures during construction:

Crosswind Substation - DRAFT Project No. 2679.01 1 June 2023



- Capturing water from low permeability surfaces and directing it away from bare soil exposures.
- Erosion control BMP inspection and maintenance: The contractor should be aware that inspection and maintenance of erosion control BMPs is critical toward their satisfactory performance. Repair and/or replacement of dysfunctional erosion control elements should be anticipated.
- Undertake site preparation, excavation, and filling during periods of little or no rainfall.
- Cover excavation surfaces with anchored plastic sheeting if surfaces will be left exposed during wet weather.
- Cover soil stockpiles with anchored plastic sheeting.
- Provide an all-weather quarry spall construction site entrance.
- Provide for street cleaning on an as-needed basis.
- Protect exposed soil surfaces that will be subject to vehicle traffic with crushed rock or crushed recycled concrete to reduce the likelihood of subgrade disturbance and sediment generation during wet weather or wet site conditions.
- Install siltation control fencing on the lower perimeter of work areas.

#### CLOSURE

The analysis and recommendations presented in this report are based, in part, on the explorations completed for this study. The number, location, and depth of the explorations were completed within the constraints of budget and site access so as to yield the information to formulate our recommendations. Project plans were in the preliminary stage at the time this report was prepared. We therefore recommend we be provided an opportunity to review the final plans and specifications when they become available in order to assess that the recommendations and design considerations presented in this report have been properly interpreted and implemented into the project design.

The performance of earthwork, structural fill, foundations, and pavements depends greatly on proper site preparation and construction procedures. We recommend that Zipper Geo Associates, LLC be retained to provide geotechnical engineering services during the earthwork-related construction phases of the project. If variations in subsurface conditions are observed at that time, a qualified geotechnical engineer could provide additional geotechnical recommendations to the contractor and design team in a timely manner as the project construction progresses.

This report has been prepared for the exclusive use of Snohomish County PUD No. 1, and its agents, for specific application to the project discussed and has been prepared in accordance with generally accepted geotechnical engineering practices. No warranties, express or implied, are intended or made. Site safety, excavation support, and dewatering requirements are the responsibility of others. In the event that changes in the nature, design, or location of the project as outlined in this report are planned, the conclusions and recommendations contained in this report shall not be considered valid unless ZGA reviews the changes and either verifies or modifies the conclusions of this report in writing.



### APPENDIX A FIELD EXPLORATION PROCEDURES AND LOGS

#### FIELD EXPLORATION AND TESTING PROCEDURES AND LOGS

Our field exploration program for this project included completing a visual reconnaissance of the site, excavating eleven test pits (TP-1 through TP-11) and advancing one hand auger boring (HA-1). The approximate exploration locations are presented on Figure 1, the *Site and Exploration Plan*. Exploration locations were determined in the field using steel and fiberglass tapes by measuring distances from existing site features shown on the *Site Plan Preliminary* plan, Sheet A1.1, dated 20 December 2022, provided by the District. The approximate ground surface elevation at the exploration locations was interpolated from contours shown on Sheet SV1.08, *North County Community Office*, dated 22 March 2022. As such, the exploration locations and elevations should be considered accurate to the degree implied by the measurement method. The following sections describe our procedures associated with the explorations. Descriptive logs of the explorations are enclosed in this appendix.

#### **Test Pit Procedures**

An independent contractor (Northwest Excavation & Trucking) working under subcontract to ZGA excavated the test pits through the use of a tracked excavator. An engineering geologist from ZGA continuously observed the test pit excavations, logged the subsurface conditions, and obtained representative soil samples. The samples were stored in moisture tight containers and transported to our laboratory for further visual classification and testing.

The enclosed test pit logs indicate the vertical sequence of soils and materials encountered in each test pit, based primarily on our field classifications and supported by our subsequent laboratory testing. Where a soil contact was observed to be gradational or undulating, our logs indicate the average contact depth. We estimated the relative density and consistency of *in situ* soils by means of the excavation characteristics and by the sidewall stability. Our logs also indicate the approximate depths of any sidewall caving or groundwater seepage observed in the test pits, as well as all sample numbers and sampling locations.

#### **Hand Auger**

Hand auger boring HA-1 was advanced using a post hole digger and 3.25-inch diameter hand auger. An engineering geologist from ZGA performed the exploration. Samples were obtained as cuttings when the soil composition changed, stored in moisture-tight containers, and transported to our laboratory for further visual classification and testing.

The enclosed hand auger log indicates the vertical sequence of soils and materials encountered in the hand auger, based primarily on our field classifications and supported by our subsequent laboratory testing. Where a soil contact was observed to be gradational or undulating, our logs indicate the average contact depth. We estimated the relative density and consistency of *in situ* soils by means of the excavation characteristics. Our log also indicates the approximate depths of groundwater observed in the exploration, as well as all sample numbers and sampling locations.

#### Sample Screening

The boring and test pit logs also include the results of sample container headspace measurements taken with a RAE Systems photoionization detector (PID). The measurements indicate the relative concentration of petroleum hydrocarbons in the headspace air, but do not identify the type of hydrocarbon. The sample headspace readings, recorded as hydrocarbon concentration in parts per million (ppm) are presented on the logs in this appendix. The sample screening did not detect hydrocarbon levels of concern.

#### **Cone Penetrometer Testing**

Cone penetrometer test CPT-1 was completed by a ZGA subcontractor (In Situ Engineering) using a truckmounted rig during a geotechnical exploration of the proposed Crosswind substation site, located in the southeastern portion of the Special Use Permit site. The testing was completed in general accordance with ASTM D 5778-12 procedures. The cone penetrometer testing involves advancing 35.7-millimeter diameter rods equipped with a friction sleeve, standard area cone, load cell, and pressure transducer. The apparatus is advanced via hydraulic pressure and the tip resistance and friction are recorded continuously. Pore pressure measurements and shear wave and compression wave testing may be taken at selected intervals. The enclosed cone penetrometer test log indicates the recorded tip resistance, friction, friction ratio, pore pressure, correlation to the Standard Penetration Test, and a graphic representation of the soil type.

### **Exploration Logs by Others**

The 29 December 2017 GeoEngineers report *Geotechnical Engineering Services, North County Project, Arlington, Washington* (File No. 0482-051-03) includes the logs of numerous explorations completed at the Microgrid site. This appendix includes the logs of six borings/monitoring wells that GeoEngineers completed within the limits of the Special Use Permit site, the approximate locations of which are illustrated on Figure 1.

	Hand Auger HA-1	Project:		North	County SUP
	Location: See Site and Exploration Plan, Figure 1	Project Nu	mber:		2679.01A
	Approximate GSE: 135 feet	Date Excav	ated:		4.25.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, red-brown, silty SAND with gravel, trace organics, root hairs; subrounded gravel. ESU-2 (FILL)	S-1 @ 0.5 feet	0.0		ACM
2	Loose, moist, brown, SILT with sand, some gravel, some organics, root hairs; fine subrounded gravel. ESU-2 (Relic	S-2 @	0.0	30	GSA CEC
3	Topsoil) CEC = 6.7 Loose to medium dense, moist, yellow-brown, SAND with	S-3 @ 2.5 feet	0.0		
4	gravel, some slit; fine subrounded gravel. ESU-3 (Qvrm)	S-4 @ 3.5 feet	0.0	11	GSA
5	Medium dense, wet to saturated, grey, poorly graded				
6	SAND with gravel; fine subangular to subrounded gravel. ESU-4	S-5 @ 5 feet	0.0		
7	Exploration completed at approximately 6.5 feet.	S-6 @ 6 feet	0.0		
8	Rapid groundwater seepage observed at 5.5 feet at time of excavation				
9					
10					
11					
12					
13					
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	<u>Test Pit TP-1</u>	Project:		North County SUP	
	Location: See Site and Exploration Plan, Figure 1	Project Nur	nber:		2679.01A
	Approximate GSE: 133 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, red-brown, silty SAND to sandy SILT, fine roots, root hairs. ESU-1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
2	Loose, moist, orange, silty SAND trace organics, roots, root hairs; some Fe; moderately weathered. ESU-3 (Qvrm) Organic Content = 5.6%	S-2 @ 2 feet	0.0		OC
4	Loose to medium dense, moist, tan, poorly graded SAND, trace silt, trace gravel; subrounded gravel. ESU-3	S-3 @ 3.5 feet	0.0	7.7	GSA
5					
6					
7	Medium dense, moist, grey brown, poorly graded GRAVEL with sand; subrounded gravel; medium dense to dense at	S-6 @ 6 feet	0.0		
	8.5 feet. ESU-4				
8					
9					
10	Exploration completed at approximately 9 feet.				
11	No groundwater seepage observed at time of excavation				
	Slight caving observed from approximately 3 feet.				
12	•				
13					
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	Test Pit TP-2	Project:		North County SUP	
	Location: See Site and Exploration Plan, Figure 1	Project Nu	mber:		2679.01A
	Approximate GSE: 133 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, red-brown, silty SAND to sandy SILT, roots, root hairs. ESU-1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
		-			
2	Loose, moist, orange, silty SAND trace coarse gravel; some Fe; moderately weathered. ESU-3 (Qvrm)	S-2 @ 2 feet	0.0		
5	Medium dense, moist, tan, poorly graded SAND trace to	21000			
4	some gravel; becomes medium dense to dense poorly graded SAND with gravel, trace silt at 3 feet; subrounded gravel. ESU-4	S-3 @ 3.5 feet	0.0	5.4	GSA
5					
6					
7					
8					
9		S-4 @	0.0		
10		9 feet			
10	Exploration completed at approximately 9.5 feet.				
11	No groundwater seepage observed at time of excavation				
12	Moderate caving observed from approximately 3 feet.				
13					
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	<u>Test Pit TP-3</u>	Project:		North	County SUP
	Location: See Site and Exploration Plan, Figure 1	Project Nur	nber:		2679.01A
	Approximate GSE: 134 feet	Date Excava	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, brown, sandy SILT to silty SAND, roots, root hairs. ESU-1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
2					
3	Loose, moist, orange, silty SAND trace coarse gravel; some Fe; moderately weathered. ESU-3 (Qvrm)	S-2 @ 2 feet	0.0		
4		 			
5	Medium dense, moist, grey, poorly graded SAND with gravel; subrounded gravel. ESU-4	S-3 @	0.0		
6		4.5 1661			
7					
8					
9		S-4 @ 9 feet	0.0		
10	Exploration completed at approximately 9.5 feet.				
11	No groundwater seepage observed at time of excavation				
12	Moderate caving observed from approximately 3 feet.				
13					
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	<u>Test Pit TP-4</u>	Project:		North County SUP	
	Location: See Site and Exploration Plan, Figure 1	Project Nu	mber:		2679.01A
	Approximate GSE: 134 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, brown, sandy SILT, fine to medium roots, root hairs. ESU 1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
2	Loose, moist, orange, SAND with silt, fine roots, root hairs, some Fe; moderately weathered. ESU 3 (Qvrm)	S-2 @ 1.5 feet	0.0		GSA
3					
4	Medium dense, moist, yellow-grey, poorly graded SAND trace gravel; with gravel at 6 feet, trace silt at 9.5 feet, with	S-3 @ 3.5 feet	0.0		
-	cobbles at 9.5 feet; subrounded cobbles; subrounded gravel. ESU 4				
5					
6					
7		S-4 @ 6 feet	0.0		
8					
9					
10		S-5 @ 9.5 feet	0.0		
11	Exploration completed at approximately 10 feet.				
12	No groundwater seepage observed at time of excavation				
13	Moderate caving observed from approximately 3 feet.				
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	Test Pit TP-5	Project:		North	County SUP
	Location: See Site and Exploration Plan, Figure 1	Project Nur	nber:		2679.01A
	Approximate GSE: 134 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, brown, sandy SILT trace gravel, fine roots, root hairs; coarse subrounded gravel. ESU -1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
2	Loose, moist, orange, poorly graded SAND with silt, trace				
3	gravel, with organics, roots, root hairs, some Fe; moderately weathered. ESU -3 (Qvrm)	S-2 @ 2.5 feet	0.0		GSA
4					
5	Medium dense moist grey-brown poorly graded SAND	S-3 @ 4.5 feet	0.0		
6	Medium dense, moist, grey-brown, poorly graded SAND with gravel, becomes medium dense to dense at 10 feet,				
	becomes moist to wet at 10 feet; subrounded gravel. ESU-				
7					
8					
9		S-4 @ 8 feet	0.0		
10					
10		S-5 @ 10 feet	0.0		
	Exploration completed at approximately 10.5 feet.				
12	No groundwater seepage observed at time of excavation				
13	Moderate caving observed from approximately 3 feet.				
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	<u>Test Pit TP-6</u>	Project:		North	County SUP
	Location: See Site and Exploration Plan, Figure 1	Project Nu	mber:		2679.01A
	Approximate GSE: 134 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, brown, silty SAND with gravel, fine roots, root hairs; coarse subrounded gravel. ESU-1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
2					
3	organics, roots, root hairs, some Fe; moderately weathered. ESU-3 (Qvrm)	S-2 @ 2.5 feet	0.0	14.9	GSA
4					
5		S-3 @ 4 feet	0.0		
	Medium dense, moist, grey-brown, poorly graded SAND				
6	trace to some gravel, trace silt at 4 feet; subrounded gravel. ESU-4	S-4 @			
7		6 feet	0.0		
8					
9		S-5 @ 8.5 feet	0.0		
10	Exploration completed at approximately 9 feet.				
10					
11	No groundwater seepage observed at time of excavation				
12	Mild caving observed from approximately 3 feet.				
13					
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	Test Pit TP-7	Project:		North	County SUP
	Location: See Site and Exploration Plan, Figure 1	Project Nu	mber:		2679.01A
	Approximate GSE: 134 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, dark brown, sandy SILT, fine roots, root hairs, some glass and plastic debris. ESU-2 (FILL)	S-1 @ 0.5 feet	0.0		ACM
2					
3	Loose, moist, orange, sandy SILT to silty SAND trace to some organics, fine roots, root hairs, some Fe; moderately				
4	weathered. ESU-3 (Qvrm) Organic Content = 6.7% CEC = 12	S-2 @ 3 feet	0.0	23.6	GSA/CEC/ OC
5					
	Medium dense, moist, grey, SAND with silt, trace gravel;				
6	subrounded gravel. ESU-4				
7					
8		S-3 @ 7 feet	0.0		
٩					
9					
10		S-5 @ 9.5 feet	0.0		
11	Exploration completed at approximately 10 feet.				
12	No groundwater seepage observed at time of excavation				
13	Moderate caving observed from approximately 4 feet.				
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	

	Test Pit TP-8	Project:		North County SUP	
	Location: See Site and Exploration Plan, Figure 1	Project Nu	mber:		2679.01A
	Approximate GSE: 134 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, dark brown, sandy SILT, medium to fine roots, root hairs. ESU-1 (Topsoil)	S-1 @ 0.5 feet	0.0		ACM
2	Loose, moist, orange, SAND with silt, trace gravel, trace to some organics, fine roots, root hairs, some Fe; moderately				
3	weathered. ESU-3 (Qvrm) Organic Content = 3.4% CEC = 5.2	S-2 @ 2 feet	0.0	20.1	GSA/CEC/O C
4	Loose to medium dense, moist, grey-brown, poorly graded SAND some gravel, trace silt; subrounded gravel. ESU-3	S-3 @ 3 feet	0.0	6.8	GSA
5					
6					
7	with gravel with cobbles at 10 feet; subrounded cobbles; subrounded gravel. ESU-4	S-4 @ 6.5 feet	0.0		
8					
9					
10					
11	Exploration completed at approximately 10.5 feet.	S-5 @ 10 feet	0.0		
12	No groundwater seepage observed at time of excavation				
13	Severe caving observed from approximately 3-3.5 feet.				
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	nillion (p	pm).	

	<u>Test Pit TP-9</u>	Project:		North	County SUP	
	Location: See Site and Exploration Plan, Figure 1	Project Nu	nber:		2679.01A	
	Approximate GSE: 135 feet	Date Excav	ated:	4.24.2023		
Depth (ft)	Material Description	Sample	PID	% M	Testing	
1	Loose, moist, red-brown, silty SAND with gravel; subrounded gravel. ESU-2 (FILL)	S-1 @ 0.5 feet	0.0		ACM	
2						
3	Loose maint vallow brown poorly graded SAND with					
	gravel, some silt; subrounded gravel; slightly weathered.	S-2 @	0.0		GSA	
4	ESU-3 (Qvrm)	3 feet				
5						
6	Loose to medium dense, wet, grey, poorly graded SAND with gravel: subrounded gravel. FSU -3	520				
0		5.5 feet	0.0			
7	Loose to medium dense, saturated, grey, poorly graded					
	GRAVEL with sand; subrounded gravel. ESU-3	S-4 @	0.0			
8		7 feet	0.0			
9	Exploration completed at approximately 8 feet					
10						
10	Rapid groundwater seepage observed at 5.5 feet at time of					
11						
	Moderate caving observed from approximately 5.5 feet.					
12						
13						
1.4						
14			L			
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).		

	Test Pit TP-10	Project:		North County SUP		
	Location: See Site and Exploration Plan, Figure 1	Project Nu	nber:		2679.01A	
	Approximate GSE: 136 feet	Date Excav	ated:	4.24.2023		
Depth (ft)	Material Description	Sample	PID	% M	Testing	
1	Loose, moist to wet, black, sandy SILT with cobbles, wood, branches, plastic, glass, metal; subrounded cobbles. ESU-2	S-1 @ 0.5 feet	0.0		ACM	
2						
3	Loose, moist to wet, yellow-brown, poorly graded SAND with gravel, some silt, some wood, branches; subrounded gravel. ESU-2 (FILL) Organic Content = 1.6% CEC = 3.3	S-2 @ 2.5 feet	0.0	9.3	GSA OC	
4						
5	Medium dense, wet to saturated, yellow-brown, gravelly					
6	SAND trace silt; subrounded gravel. ESU-4 (Qvrm)	S-3 @ 5.5 feet	0.0	8.2	GSA	
7						
/	Exploration completed at approximately 6 feet.					
8	Rapid groundwater seepage observed at 5 feet at time of					
9	Slight caving observed from approximately 3 feet.					
10						
11	•					
12						
13						
14						
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).		

	Test Pit TP-11	Project:		North	County SUP
	Location: See Site and Exploration Plan, Figure 1	Project Nu	nber:		2679.01A
	Approximate GSE: 136 feet	Date Excav	ated:		4.24.2023
Depth (ft)	Material Description	Sample	PID	% M	Testing
1	Loose, moist, brown to tan, SAND with silt, with gravel, fine to medium roots, root hairs, plastic, metal pipes. ESU-2	S-1 @ 0.5 feet	0.0	17.6	ACM/GSA/ CEC/OC
2	(FILL) Organic Content = 4.7% CEC = 6.2				
3	Loose, moist to wet, grey-brown, poorly graded SAND with gravel, some Fe; subrounded gravel; moderately weathered.	S-2 @ 2.5 feet	0.0		
4					
5	Medium dense, wet to saturated, grey-brown, poorly graded SAND with gravel to gravely SAND trace silt:				
6	subrounded gravel. ESU-4				
-					
/					
8					
9		S-3 @ 8 feet	0.0	10.3	GSA
10	Exploration completed at approximately 8.5 feet				
	Rapid groundwater seepage observed at 8 feet at time of				
11	excavation				
12	Mild to moderate caving observed from approximately 4.5 feet.				
13					
14					
	Note: PID is the displayed hydrocarbon concentration in	parts per m	illion (p	pm).	



CPT-01

CPT Contractor: In Situ Engineering CUSTOMER: ZipperGeo LOCATION: Arlington JOB NUMBER: 2679.01 OPERATOR: Forinash CONE ID: DDG1351 TEST DATE: 2/24/2023 9:46:02 AM Coring: 0ft Backfill: 20% Bentonite Slurry + Bentonite Chip Surface Patch: None



**GeoEngineers Exploration Logs** 





Project Location: Project Number: 0482-051-03

0482051\GINT\048205

Date

Figure A-5 Sheet 1 of 1





Project Location: Arlington, Washington Project Number: 0482-051-03

llingham:

Start       End       Total       Depth (ft)       26.5       Log Cher         brilled       3/8/2017       3/8/2017       Depth (ft)       26.5       Log							Logged By Checked By	NS KMS	Driller Holocene Dri	illing, Ir	nc.	Drilling Method Hollow-stem Auger					
Hammer Autohammer Data 140 (lbs) / 30 (in) Drop								E	Drilling Diedrich D50 Track-mounted D0E Well I.D.: BJY260 A 2 (in) well was installed on 3/8/2017 to a de				to a depth of 20 (ft).				
Surrace Elevation (ft)       133         Vertical Datum       NAVD88								E	Top of Casing 133 Elevation (ft)			<u>Ground</u>	<u>water</u>	D	epth to	Claustice (A)	
Lasting (X)       1319707         Northing (Y)       424320								F	Horizontal WA State Plane North Datum NAD83 (feet)				4/13/2	2017	Water (ft) El   8.3 2		124.7
Notes:		Enviro noted	onment	al field:	l screeni	ngv	vas c	omple	ted on each so	il sample	. Sheen and head space	ce vapo	or were	not ob	served ur	nless other	rwise
FIELD DATA											WELL LOG						
Elevation (fee	ueptn (reet)	Interval Recovered (in	Blows/foot	Collected Sampl	<u>Sample Name</u> Testing	Water Level	Graphic Log	Group Classification		N DES	IATERIAL SCRIPTION		Moisture Content (%)	Fines Content (%)	E.		Steel surface monument
<sup>29</sup>		18	16	(1	1 <u>B-10-2.5)</u> %F; CA			TS SM SP-SM	Topsoil wit Dark brow roots (1 Light brow dense, (Slight she	h roots n silty fine copsoil) n fine to m moist) (re- en)	sand with organic matter, edium sand with silt (mec cessional outwash)	dium	8	5	2.0 <i>—</i> 3.0 <i>—</i>		Concrete surface seal Bentonite
ł	5	12	36	ĹĔ	2 <u>B-10-5.0)</u> SA; CA		-	SP-SM	( <u>Moderate</u> Brown fine	sheen; PII to mediur	0 <u>2.8 ppm)</u> n sand with silt and (dense, moist)	^	6	7	5.0—		PVC well casing
<sup>2</sup> <sup>2</sup>	  -  -	14	45	(E	<u>3</u> B <u>-10-7.5)</u> MC; CA	Ţ		SP	Gravel in sl (Slight she Gray fine to	hoe en, PID <1 o coarse sa	ppm)	oist)	4				
ης Γ		17	41		4 %F				_ Becomes w	vet		-	11	3			
۲۵ ۲5 ۲۶		18	55		6				- - - Becomes v -	ery dense		-  - -					PVC screen, 0.02-inch slot widt
20		6	25		7	•		SP-SM	Brown fine dense, v	 to medium wet)	sand with silt (medium	- - - -			20.0 <u>–</u> 20.2		2-inch Schedule 4 PVC end cap
25			36		<u>8</u> %F				E Becomes de	ense		-	19	11			
Note: Se Coordin	ee Fi aates	gure A- Data S	1 for ex jource: 1	planatic	on of sym	bols. kima	ted ba	ased on	Hand-held GPS	(±18 ft), V	ertical approximated base	ed on Su	urvey Bas	semap (	±1 ft)		
									Log	of Bo	ring B-10						
								~	Project:	Arlingto	n Local Office Repla	acem	ent				
Ge	0	EN	IGI	NE	ERS	1			Project Lo	cation:	Arlington, Washing	gton					Figure A-5

Project Number: 0482-051-03

Figure A-5 Sheet 1 of 1



Project Number: 0482-051-03

Figure A-6 Sheet 1 of 1 APPENDIX B LABORATORY TESTING PROCEDURES AND RESULTS

### LABORATORY PROCEDURES AND RESULTS

A series of laboratory tests were performed during the course of this study to evaluate the index and geotechnical engineering properties of the subsurface soils. Descriptions of the types of tests performed are given below.

#### **Visual Classification**

Samples recovered from the exploration locations were visually classified in the field during the exploration program. Representative portions of the samples were carefully packaged in moisture tight containers and transported to our laboratory where the field classifications were verified or modified as required. Visual classification was generally done in accordance with ASTM D 2488. Visual soil classification includes evaluation of color, relative moisture content, soil type based upon grain size, and accessory soil types included in the sample. Soil classifications are presented on the exploration logs in Appendix A.

#### **Moisture Content Determinations**

Moisture content determinations were performed on representative samples obtained from the explorations in order to aid in identification and correlation of soil types. The determinations were made in general accordance with the test procedures described in ASTM D 2216. The results are shown on the exploration logs in Appendix A.

#### **Grain Size Analysis**

A grain size analysis indicates the range in diameter of soil particles included in a particular sample. Grain size analyses were performed on representative samples in general accordance with ASTM D 6913. The results of the grain size determinations for the samples were used in classification of the soils, and are presented in this appendix.

#### **Atterberg Limits**

Atterberg limits are used primarily for classification and indexing of cohesive soils. The liquid and plastic limits are two of the five Atterberg limits and are defined as the moisture content of a cohesive soil at arbitrarily established limits for liquid and plastic behavior, respectively. Liquid and plastic limits were established for selected samples in general accordance with ASTM D 423 and ASTM D 424, respectively. The results of the Atterberg limits are presented on a plasticity chart in this appendix where the plasticity index (liquid limit minus plastic limit) is related to the liquid limit. The plastic limits and liquid limits are also presented adjacent to appropriate samples on the exploration logs in Appendix A.

### Asbestos Containing Material (ACM)

Five samples of existing fill material were collected from the test pits and borings in order to test for the presence of ACM. Examination of these samples was conducted for the presence of identifiable asbestos fibers using polarized light microscopy (PLM) with dispersion staining in accordance with both EPA 600/M4-82-020, Interim Method for the Determination of Asbestos in Bulk Insulation Samples and EPA 600/R-93/116 Method for the Determination of Asbestos in Bulk Building Materials. Results of the tests

are presented in the attached NVL report in this appendix. The ACM was not detected in any of the samples.

### **Cation Exchange Capacity**

Selected samples were tested for Cation Exchange Capacity (CEC) by a subcontract analytical testing laboratory (AmTest Laboratories of Kirkland, Washington). The tests were completed in general accordance with the EPA Laboratory Method 9081 testing procedure. The test results are presented in this appendix and discussed in the report text.

### **Organic Content**

The organic content of selected samples was determined in general accordance with ASTM D 2974. The results of the tests are discussed in the report text.
































#### GEOTECHNICAL ENGINEERING • ENVIRONMENTAL ENGINEERING CONSTRUCTION TESTING & INSPECTION

May 10, 2023

KA No. 096-23255 Lab Report No. 01 Page 1 of 1

Mr. David Williams(E-Mail) ZIPPER GEO ASSOCIATES LLC 19019 36<sup>th</sup> Avenue W, Suite E Lynnwood, WA 98036

### RE: SOILS LABORATORY TESTING Crosswind 4303 198<sup>th</sup> Street SW Lynnwood, Washington

Dear Mr. Williams,

In accordance with your request and authorization, we have performed laboratory tests for the above referenced project.

Laboratory testing was performed in accordance with ASTM standards. The results of the laboratory tests are presented on the following pages. If you have any questions; or if we can be of further assistance, please do not hesitate to contact our office.

82504-A	82504-B	82504-C	82504-D	82504-E
		5/8/2023		
	S	Substation: 2679.0	1	
TP-A-1 / S-2	TP-8 / S-2	TP-10 / S-2	TP-7 / S-2	TP-11/S-1
5.6%	3.4%	1.6%	6.7%	4.7%
	82504-A TP-A-1 / S-2 5.6%	82504-A 82504-B S TP-A-1 / S-2 TP-8 / S-2 5.6% 3.4%	82504-A 82504-B 82504-C   5/8/2023 Substation: 2679.0   TP-A-1 / S-2 TP-8 / S-2 TP-10 / S-2   5.6% 3.4% 1.6%	82504-A 82504-B 82504-C 82504-D   5/8/2023   Substation: 2679.01   TP-A-1 / S-2 TP-8 / S-2 TP-10 / S-2 TP-7 / S-2   5.6% 3.4% 1.6% 6.7%

(ASTM D2974)

Respectfully submitted, **KRAZAN & ASSOCIATES, INC.** Jeffrey S. Merce Operations Manager Pacific Northwest Division JSM/lkj



AmTest Chain of Custody Record 13600 NE 126<sup>th</sup> PL, Suite C, Kirkland, WA 98034 Ph (425) 885-1664 Fx (425) 820-0245 www.amtestlab.com

				WWV	v.amtest	lab.com			C	hain of	f Custo	dy No	5	0(	<u>)0</u>		
Client Name	e & Address:			· · · · · · · · · · · · · · · · ·		Invoic	e To:										
Zipper	Geo Associa	des				Zij	pper	- (se	o Ass	Socie	cles						
19019	36th Avenue	W,Sc	úł.	εE		i S c	piq	364	n Ave	enne	w,	Sus	10 8	  			
Lynnwi	ouch, WA 98	5036				Lyi	A VIV	ood	WA	99	2036	4					
Contact Perso	n: David Will	liams				Invoice	Conta	act: D	buid	Wi	Hicy	ИS					
Phone No: 425-218-4619						PO Nur	nber:	ι	125-	-218-	-46	19					
Fax No:						Invoice	Ph/Fa	ax:					.A				
E-mail: Awilliams @ Figher and Com						Invoice	e E-ma	il: chi	willie	1WLS	Øz	ippe	rgec	).(	on	4	
Report Delive	ry: (Choose all that ap	ply)	ed (	nline		Data p Web Li	osted cain II	to onli ):	ne acco	unt: `	YES /	NO					
Special Instru	Ictions:	1 1030			<u> </u>												
Requested T/	AT: (Rush must be pre-a	approved t	<b>iy la</b> Dav	b) / 48 HS	2 / 24	HR )	Tem	peratu	re upon	Recei	pt: 3	1,2%	Ċ	<u> </u>			
Project Name				7 10 11	<u> </u>		10			Analy	/sis Re	queste	ed	dealling comm			
LYOSSU Project Numb	and Substati	101		eđ	led		liner	T							T		
	26 19.01			dug	dme	ž	Intai										
AmTest ID	Client ID, (35 characters ma	ıx)		Date Si	Time 9	Time 9	Mai	No. of co	CFC								QA/QC
7661	TP-7, S-2		4	24/23			1	$\mathbf{X}$									
7662	TP-8, S-7		41	24/23			1	$\bowtie$									
763	TP-10, 8-2		4	24/23			1	$\boxtimes$									
7669	TP-11, S-1		4	24/23			۱	$\bowtie$									
7665	HA-1, S-2		4	25/23			- \ `	$\mathbb{X}$									
			ļ														
																_,	
					<u> </u>	_	<u>.</u>										
Collected/Relin	ngulshed By:	Date	<u> </u>	Time	Receiv	ed By:	΄μ					Date	 √/2	~	Tim	ie Z	
Dereil	lleann	17.28.2	2,3	TPA	Deceiv	ed By:	·/ I				······.	7/2 Date	92		Tim		
Keiinquisneo E	<del>.</del>	Date		rane	I INCLEIV	<b>cu vy</b> .			-			Date:					
Relinquished E	Зу:	Date		Time	Receiv	ed By:						Date			Tim	ie	
		<u> </u>											<u></u>				

COMMENTS:

Am Test Inc. 13600 NE 126TH PL Suite C Kirkland, WA 98034 (425) 885-1664 www.amtestlab.com



Professional Analytical Services

### **ANALYSIS REPORT**

ZIPPER GEO ASSOCIATES, LLC 19019 36TH AVENUE W LYNNWOOD, WA 98036 Attention: DAVID WILLIAMS Project Name: CROSSWIND SUBSTATION Project #: 2679.01 All results reported on an as received basis. Date Received: 04/28/23 Date Reported: 5/ 9/23

AMTEST Identification Number	23-A007661
Client Identification	TP-7,S-2
Sampling Date	04/24/23

### Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	12.	meq/100g		0.5	SW-846 9081	СМ	05/03/23

AMTEST Identification Number	23-A007662
Client Identification	TP-8,S-2
Sampling Date	04/24/23

### Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	5.2	meq/100g		0.5	SW-846 9081	СМ	05/03/23

AMTEST Identification Number	23-A007663
Client Identification	TP-10,S-2
Sampling Date	04/24/23

# Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	3.3	meq/100g		0.5	SW-846 9081	СМ	05/03/23

AMTEST Identification Number	23-A007664
Client Identification	TP-11,S-1
Sampling Date	04/24/23

### Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	6.2	meq/100g		0.5	SW-846 9081	СМ	05/03/23

AMTEST Identification Number	23-A007665
Client Identification	HA-1,S-2
Sampling Date	04/24/23

### Conventionals

PARAMETER	RESULT	UNITS	Q	D.L.	METHOD	ANALYST	DATE
Cation Exchange Capacity	6.7	meq/100g		0.5	SW-846 9081	СМ	05/03/23

) Infl Kathy Fugiel President

Am Test Inc. 13600 NE 126th PL Suite C Kirkland, WA, 98034 (425) 885-1664 www.amtestlab.com



QC Summary for sample numbers: 23-A007661 to 23-A007665

### DUPLICATES

SAMPLE #	ANALYTE	UNITS	SAMPLE VALU	IE  DUP VALUE	RPD
23-A007665	Cation Exchange Capacity	meq/100g	6.7	7.0	4.4
		<b>C</b>			
STANDARL	REFERENCE MATERIAL	5			
ANALYTE		UNITS	TRUE VALUE	MEASURED VALUE	RECOVERY
Cation Exchai	nge Capacity	meq/100g	2.0	2.0	100. %
BLANKS					
ANALYTE		UNITS	RESULT		
Cation Excha	nge Capacity	meq/100g	< 0.2		

April 28, 2023



Justin Brooks Zipper Geo Associates, LLC 19019 36th Avenue West, Suite E Lynnwood, WA 98036

#### RE: Bulk Asbestos Fiber Analysis; NVL Batch # 2306722.00

Client Project: 2679 Crosswind SubStation Location: Arlington

Dear Mr. Brooks,

Enclosed please find test results for the 12 sample(s) submitted to our laboratory for analysis on 4/26/2023.

Examination of these samples was conducted for the presence of identifiable asbestos fibers using polarized light microscopy (PLM) with dispersion staining in accordance with **U. S. EPA 40 CFR Appendix E to Subpart E of Part 763**, Interim Method for the Determination of Asbestos in Bulk Insulation Samples and **EPA 600/R-93/116**, Method for the Determination of Asbestos in Bulk Building Materials.

For samples containing more than one separable layer of materials, the report will include findings for each layer (labeled Layer 1 and Layer 2, etc. for each individual layer). The asbestos concentration in the sample is determined by calibrated visual estimation.

For those samples with asbestos concentrations between 1 and 10 percent based on visual estimation, the EPA recommends a procedure known as point counting (NESHAPS, 40 CFR Part 61). Point counting is a statistically more accurate means of quantification for samples with low concentrations of asbestos.

The detection limit for the calibrated visual estimation is <1%, 400 point counts is 0.25% and 1000 point counts is 0.1%

Samples are archived for two weeks following analysis. Samples that are not retrieved by the client are discarded after two weeks.

Thank you for using our laboratory services. Please do not hesitate to call if there is anything further we can assist you with.

Sincerely,

Nick Ly, Technical Director

Testing

Enc.: Sample Results

Phone: 206 547.0100 | Fax: 206 634.1936 | Toll Free: 1.888.NVL.LABS (685.5227) 4708 Aurora Avenue North | Seattle, WA 98103-6516



By Polarized Light Microscopy

Client: Zipper Geo Associates, LLC Address: 19019 36th Avenue West, Suite E Lynnwood, WA 98036 Batch #: 2306722.00 Client Project #: 2679 Crosswind SubStation Date Received: 4/26/2023 Samples Received: 12 Samples Analyzed: 12 Method: EPA/600/R-93/116

Attention: Mr. Justin Brooks

Project Location: Arlington

2

Lab ID: 2304	1630 Client Sample #: TP 1		
Location: Arlin	ngton		
Comments:	Qualitative analysis was conducted for the preser		
Layer 1 of 1	<b>Description:</b> Loose brown crumbly material wit	h debris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine particles, Fine grains	Cellulose	None Detected ND
	Mineral grains, Organic debris		
Lab ID: 2304	1631 Client Sample #: TP.2		
Location: Arlir	ngton		
Comments:	Qualitative analysis was conducted for the preser	nce of asbestos fibers in this sample.	
Layer 1 of 1	Description: Loose tan crumbly material with d	ebris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine grains, Fine particles	Cellulose	None Detected ND
	Mineral grains, Organic debris		
Lab ID: 2304	1632 Client Sample #: TP.3		
Location: Arlin	ngton		
Comments:	Qualitative analysis was conducted for the preser	nce of asbestos fibers in this sample.	
Layer 1 of 1	Description: Loose brown crumbly material wit	h debris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Mineral grains, Fine particles	Cellulose	None Detected ND
	Fine grains, Organic debris	Wood fibers	
Lab ID: 2304 Location: Arlin	1633 Client Sample #: TP.4		

Comments: Qualitative analysis was conducted for the presence of asbestos fibers in this sample.

Reviewed by: Nick Ly	Date: 04/28/2023	Nick Ly, Technical Director
Analyzed by: Hilary Crumley	Date: 04/28/2023	
Sampled by: Client		Interes



By Polarized Light Microscopy

Client: Zipper Geo Associates, LLC Address: 19019 36th Avenue West, Suite E Lynnwood, WA 98036

Attention: Mr. Justin Brooks

Project Location: Arlington

Batch #: 2306722.00 Client Project #: 2679 Crosswind SubStation Date Received: 4/26/2023 Samples Received: 12 Samples Analyzed: 12 Method: EPA/600/R-93/116

Layer 1 of 1	Description: Loose brown crumbly m	naterial with debris		
	Non-Fibrous Mate	erials: Other F	ibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine particles, Mineral g	rains	Wood fibers	None Detected ND
	Fine grains, Organic d	lebris	Cellulose	
Lab ID: 2304	1634 Client Sample #: TP.5			
Location: Arlin	gton			
Comments:	Qualitative analysis was conducted for	the presence of asbe	stos fibers in this sample.	
Layer 1 of 1	Description: Loose dark brown crum	bly material with debr	is	
	Non-Fibrous Mate	erials: Other F	ibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine grains, Mineral g	rains	Cellulose	None Detected ND
	Fine particles, Organic d	lebris		
Lab ID: 2304 <sup>2</sup>	1635 Client Sample #: TP.6			
Location: Arlin	gton			
Comments:	Qualitative analysis was conducted for	the presence of asbe	stos fibers in this sample.	
Layer 1 of 1	Description: Loose brown crumbly m	naterial with debris		
	Non-Fibrous Mate	erials: Other F	ibrous Materials:%	Asbestos Type: %
	Binder/Filler, Mineral grains, Fine g	rains	Cellulose	None Detected ND
	Fine particles, Organic d	lebris		
Lab ID: 2304	1636 Client Sample #: TP.7			
Location: Arlin	gton			
Comments:	Qualitative analysis was conducted for	the presence of asbe	stos fibers in this sample.	
Layer 1 of 1	Description: Loose dark brown crum	bly material with debr	is	
	Non-Fibrous Mate	erials: Other F	ibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine particles, Fine g	rains	Cellulose	None Detected ND
	Mineral grains, Organic d	lebris	Wood fibers	
Sampled b	<b>by:</b> Client		An =	
Analyzed b	<b>y:</b> Hilary Crumley	Date: 04/28/2023		
Reviewed b	by: Nick Ly	Date: 04/28/2023	Nick Ly, Tech	inical Director
Note: If samples a	re not homogeneous then subsamples of the co	moonents were analyzed	senarately. All hulk samples ar	in analyzed using both EBA



By Polarized Light Microscopy

Client: Zipper Geo Associates, LLC Address: 19019 36th Avenue West, Suite E Lynnwood, WA 98036 Batch #: 2306722.00 Client Project #: 2679 Crosswind SubStation Date Received: 4/26/2023 Samples Received: 12 Samples Analyzed: 12 Method: EPA/600/R-93/116

Attention: Mr. Justin Brooks

Project Location: Arlington

2

	4627 Client Completty TB 9		
Lab ID: 2304	Glient Sample #: 1P.0		
Comments:	Qualitative analysis was conducted for the prese	nce of asbestos fibers in this sample.	
Layer 1 of 1	<b>Description:</b> Loose brown crumbly material wit	th debris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine grains, Fine particles	Cellulose	None Detected ND
	Mineral grains, Organic debris		
Lab ID: 2304	1638 Client Sample #: TP.9		
Location: Arlin	ngton		
Comments:	Qualitative analysis was conducted for the prese	nce of asbestos fibers in this sample.	
Layer 1 of 1	Description: Loose tan crumbly material with c	debris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine grains, Mineral grains	Cellulose	None Detected ND
	Fine particles, Debris		
Lab ID: 2304	1639 Client Sample #: TP.10		
Location: Arlin	ngton		
Comments:	Qualitative analysis was conducted for the prese	nce of asbestos fibers in this sample.	
Layer 1 of 1	Description: Loose brown crumbly material with	th debris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Mineral grains, Fine grains	Cellulose	None Detected ND
	Fine particles, Organic debris		
Lab ID: 2304	1640 Client Sample #: TP.11		
Location: Arlin	ngton		

Comments: Qualitative analysis was conducted for the presence of asbestos fibers in this sample.

Reviewed by: Nick Ly	Date: 04/28/2023	Nick Ly, Technical Director
Analyzed by: Hilary Crumley	Date: 04/28/2023	
Sampled by: Client		Deter



By Polarized Light Microscopy

Client: Zipper Geo Associates, LLC Address: 19019 36th Avenue West, Suite E Lynnwood, WA 98036 Batch #: 2306722.00 Client Project #: 2679 Crosswind SubStation Date Received: 4/26/2023 Samples Received: 12 Samples Analyzed: 12 Method: EPA/600/R-93/116

Attention: Mr. Justin Brooks

Project Location: Arlington

Layer 1 of 1	Description: Loose brown crumbly material wit	h debris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Fine particles, Fine grains	Cellulose	None Detected ND
	Mineral grains, Organic debris		
Lab ID: 2304	1641 Client Sample #: HA.1		
Location: Arlir	ngton		
Comments:	Qualitative analysis was conducted for the preser	nce of asbestos fibers in this sample	е.
Layer 1 of 1	Description: Loose tan crumbly material with d	lebris	
	Non-Fibrous Materials:	Other Fibrous Materials:%	Asbestos Type: %
	Binder/Filler, Mineral grains, Fine particles	Cellulose	None Detected ND
	Fine grains, Organic debris		

Sampled by: Client		Deter	
Analyzed by: Hilary Crumley	Date: 04/28/2023	differ the second secon	_
Reviewed by: Nick Ly	Date: 04/28/2023	Nick Ly, Technical Director	

# ASBESTOS LABORATORY SERVICES



Rush Samples \_\_\_\_\_

Company	Zipper Geo Associates, LLC	N'
Address 19019 36th Avenue West, Suite E		Т/
	Lynnwood, WA 98036	R
Project Manager	Mr. Justin Brooks	D
Phone	(425) 582-9928	Er
Cell	(813) 205-3481	Fa

NVL E	Batch	Number 23	306722	2.00
TAT	3 Day	/S		AH No
Rush	TAT			
Due D	Date	5/1/2023	Time	9:00 AM
Email	jbroc	ks@zipperg	eo.com	
Fax	(425	) 582-9930		

Project Name/Number: 2679 Crosswind SubStation	Project Location: Arlington
Subcategory PLM Bulk	

Item Code ASB-02

EPA 600/R-93-116 Asbestos by PLM <bulk>

## Total Number of Samples 12

	Lab ID	Sample ID	Description	A/R
1	23041630	TP.1		А
2	23041631	TP.2		А
3	23041632	TP.3		А
4	23041633	TP.4		А
5	23041634	TP.5		А
6	23041635	TP.6		А
7	23041636	TP.7		А
8	23041637	TP.8		А
9	23041638	TP.9		А
10	23041639	TP.10		А
11	23041640	TP.11		А
12	23041641	HA.1		А

	Print Name	Signature	Company	Date	Time		
Sampled by	Client						
Relinquished by	Client						
Office Use Only	Print Name	Signature	Company	Date	Time		
Received by	Rachelle Miller		NVL	4/26/23	900		
Analyzed by	Hilary Crumley		NVL	4/28/23			
Results Called by							
Faxed Emailed							
Special Samples were dried prior to analysis. Instructions:							

# ASBESTOS LABORATORY SERVICES



Company	Zipper Geo Associates, LLC	NVL Batch	Number 2	306722	2.00 · ·	
Address	19019 36th Avenue West, Suite E Lynnwood, WA 98036	TAT 3 Da Rush TAT	ι <b>γs</b>		AH No	
Project Manager	Mr. Justin Brooks	Due Date	5/1/2023	Time	9:00 AM	
Phone	(425) 582-9928	Email jbroo	oks@zipperg	eo.com		
Cell	(813) 205-3481	Fax (425	5) 582-9930			
N 10 10 10 10 10 10 10 10 10 10 10 10 10						

Project Name/Number: 2679 Crosswind SubStation Project Location: Arlington

Subcategory PLM Bulk

Item Code ASB-02

Method EPA 600/R-93-116 Asbestos by PLM <bulk>

### Total Number of Samples 12

Rush Samples

	Lab ID	Sample ID	Description	A/R
1	23041630	TP.1		A
2	23041631	TP.2		A
3	23041632	TP.3		A
4	23041633	TP.4		A
5	23041634	TP.5		A
6	23041635	TP.6		A
7	23041636	TP.7		A
8	23041637	TP.8		A
9	23041638	TP.9		A
10	23041639	TP.10		A
11	23041640	TP.11		A
12	23041641	HA.1		A

	Print Name	Signature	Company	Date	Time
Sampled by	Client	. 11	1-	4.26.2	20850
Relinquished by	Client	N/man	Mon		
Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Rachelle Miller	PST-	– NVL	4/26/23	900
Analyzed by			NVL		
<b>Results Called by</b>					
🗌 Faxed 🗌 Emailed					
Special Instructions:					
Entered By: Rachelle Miller		Date: 4/26/2023	Time: 8:49 AM		1 of 1

APPENDIX C LIQUEFACTION ANALYSIS OUTPUT PLOT

#### Zipper Geo Associates, LLC



19019 36th Avenue West, Suite E Lynnwood, Washington (425) 582-9928

LIQUEFACTION ANALYSIS REPORT

#### **Project title : Crosswind Substation**

#### Location : Arlington, Washington









**CPT** basic interpretation plots (normalized)





